


15-169-00928-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Saline County, Sec. 8 Twp. 16 Rge. 3 (E) (W) #
Location as "NE/CNW/SE" or footage from lines C W/2 SE SW
Lease Owner Fell & Wolfe Oil Co.
Lease Name Oborg Well No. 3
Office Address P.O. Bx 7447 Tulsa, Oklahoma 74105
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 9-1 19 53
Application for plugging filed 5-24 19 74
Application for plugging approved 5-26 19 74
Plugging commenced 5-30 19 74
Plugging completed 6-3 19 74
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3437' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,266'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3437' to 3400'. Dumped 3 bx of cement. Mudded hole to 215'. Made 15' of rock bridge. Dumped 25 bx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 bx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno ss.
Reno (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June 19 74

My commission expires December 31, 1977

[Signature]
Notary Public.

15-169-00928-00-00

THE ATLANTIC REFINING COMPANY
830 Kennedy Building
Tulsa, Oklahoma

WELL LOG

Oberg No. 3

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1974
CONSERVATION DIVISION
Wichita, Kansas

Location: C W/2 SE SW of 8-16S-3W, Saline County, Kansas.

Lease Number: KS-12,175

Elevations: RKB 1373.5', DP 1371', GL 1368'.

Spudded: August 17, 1953

Reached Total Depth: September 1, 1953

Contractor: Brack Drilling Company, Inc.

Casing Record:

Ran 6 joints 13-3/8" OD 48# H-40 J&L seamless casing. Cemented 174' @ 182' RKB with 200 sacks Pozmix plus 200# calcium chloride.

Ran 10 joints 8-5/8" OD 24# J-55 ST&C casing. Cemented 397' @ 397' with 250 sacks cement. First 125 sacks contained 1/4 of 1% Flocele.

Ran 110 joints 4-1/2" OD 9.5# H-40 ST&C J&L casing. Cemented 3428.15' @ 3435' RKB with 200 sacks Pozmix.

FORMATION RECORD:

Surface soil, sand	
shale & shells	0' - 225'
Shale & shells	225' - 399'
Lime	399' - 630'
Lime & shale	630' - 2944'
Lime	2944' - 2985'
Cherty lime	2985' - 3005'
Shale & lime	3005' - 3050'
Lime	3050' - 3149'
Lime & shale	3149' - 3270'
Shale & shells	3270' - 3330'
Shale	3330' - 3420'
Shale & lime	3420' - 3437'

3437' TD

Completion:

Acidized open hole 3435'-3437' with 250 gallons Dowell XX acid plus H-38. Sandfraced. Tested 74.90 BOPD & 26.63 BWPD on September 25, 1953.
