

15-169-00927-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 8 Twp. 16 Rge. 3 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C, NE SW E
Lease Owner Rirby Petroleum Co.
Lease Name Ellen Oleen Well No. 2
Office Address 402 First National Bank Building, Pawhuska, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 15 19 53
Application for plugging filed June 8 19 65
Application for plugging approved June 9 19 65
Plugging commenced 6-5-65 19
Plugging completed 6-8-65 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production May 19, 19 65
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Viola Depth to top 3407' Bottom 3409' Total Depth of Well 3410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	166'	None
				5-1/2"	3447'	2823'
				8-5/8"	480'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3430', sanded to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2" casing, bridged hole on top of fluid @ 300', set rock bridge to 290' and dumped 25 sacks of cement. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or ~~(owner)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of June, 1965

My commission expires May 20, 1968

Milton J. Holm
Notary Public.

15-169-00927-00-00

NATIONAL ASSOCIATED PETROLEUM COMPANY
OLEEN NO. 2 - Cen. NE SW of 8-16S-3W
SALINE COUNTY, KANSAS

Drilling Contractor: Exploration Drilling Co.
220 North Boston
Tulsa, Oklahoma

Started Rigging Up : 5-20-53
Started Drilling : 5-22-53
Completed Drilling : 6-11-53

Set: 5 Joints of 10-3/4" Surface Casing
@ 166' W/125 Sacks of Cement.

Set: 116 Joints of 5-1/2"
Casing @ 3407' W/75
Sacks of Cement.

Set: 16 Joints of 8-5/8" Intermediate
Casing @ 480' W/100 Sacks of Cement.

FORMATIONS

Surface	0'	164'
Shale & Shells	164	525
Red Rock, Shale & Shells	525	555
Shale & Shells	555	660
Sand	660	750
Lime	750	1100
Sandy Shale	1100	1395
Shale	1395	1750
Shale & Lime	1750	1840
Shale	1840	1865
Lime	1865	2015
Lime & Shale	2015	2325
Sand, Shale & Lime	2325	2420
Shale & Lime	2420	2640
Lime	2640	2758
Lime & Shale	2758	2808
Lime	2808	2958
Lime & Chert	2958	3050
Lime	3050	3095
Lime & Chert	3095	3146
Lime	3146	3165
Lime & Shale	3165	3219
Shale	3219	3296
Shale & Limy Shale	3296	3409 Total Depth

CERTIFICATION

This is to certify that the above and foregoing is a true, correct, and complete copy of the Driller's Log covering the Oleen No. 2 according to the records of this office and the best of my knowledge and belief.

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1965

CONSERVATION DIVISION
Wichita, Kansas

EXPLORATION DRILLING COMPANY

By *Clair M. ...*

W. ...
Notary Public

Subscribed and sworn to before me this 3rd day of July, 1953.

My commission expires April 25, 1954.