


15-169-00722-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 8 Twp. 16S Rge. 3 (X) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/4 NW/4 NE/4
Lease Owner De Weese & Sanderson
Lease Name Applequist Well No. 1
Office Address 900 NW Third - Abilene, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 20 19 53
Application for plugging filed June 20 19 53
Application for plugging approved June 20 19 53
Plugging commenced June 20 19 53
Plugging completed June 20 19 53
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Maquoketa Dolomite	Water	3364	3457	8 5/8"	358	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

20 sacks cement At Total Depth
Heavy mud to 190'
Set bridge to 180' - 15 sacks cement
Mud to 20'
Bridge and 5 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shields Drilling Co., Inc.
Address Box 248 - Russell, Kansas

STATE OF Kansas COUNTY OF Saline ss.
J. W. Sanderson (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Sanderson
340 S Ohio - Salina, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 53
L. L. Shost Notary Public

My commission expires Sept. 4, 1954
23-8390-s 6-51-20M

8-16 3w
109 40

WELL LOG

15-169-00722-00-00

De Weese & Sanderson
APPLEQUIST #1

NW/4 NW/4 NE/4
Sec. 8, Twp 16S, Rge 3W
Saline County - Kansas

Total Depth: 3457'
Commenced: June 4, 1953
Completed: June 20, 1953
Drilled by Shields Drilling Co., Inc.

CASING RECORD

8 5/8" 350' Cmtd. w/ 250 sacks

Elevation: 1325' RB
Treatment:
Production: D & A

----- Figures Indicate Bottom of Formations -----

Surface Clay	40
Sand & Shale	60
Shale & Shells	215
Shale	300
Shale & Gyp	339
Shale	345
Chalk	350
Anhydrite Lime	415
Lime & Shale	430
Shale & Shells	485
Red Bed & Shale	520
Shale & Shells	665
Lime & Shale	1070
Broken Lime & Shale	1190
Shale, Shells & Salt	1300
Shale & Shells	1375
Lime & Shale	1510
Lime & Shale Streak	1650
Lime & Shale	1700
Lime	1770
Lime & Shale	2705
Shale	2850
Lime & Shale	2949
Shale	2960
Broken Lime	3002
Lime & Shale	3082
Shale	3098
Lime & Shale	3160
Shale	3205
Lime & Shale	3378
Lime	3393
Shale	3450
Lime & Shale	3457 TD

NOTES

Top of Maquoketa Dolomite 3364'
D & T 3365-78 - Recovered 15' drilling fluid

