

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Saline County. Sec. 33 Twp. 16 Rge. 3 (E) W (W)
Location as "NE/CNW/SE/SW" or footage from lines. NW NW NW
Lease Owner W-D Oil Co.
Lease Name Pearson Well No. 1
Office Address P. O. Box 296, Burlington, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed April 23 1968
Application for plugging approved 19
Plugging commenced May 27 1968
Plugging completed June 3 1968
Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. Toman (Finished) Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3350'. Dumped 5 sacks of cement. Shot pipe off at 2800'.
Pulled pipe and mudded hole to 300'. Set 10' rock bridge and dumped
25 sacks of cement. Mudded hole to 35'. Set 10' rock bridge and
dumped 10 sacks of cement at base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1968
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kans. COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans.

Subscribed and sworn to before me this 3rd day of June, 1968
October 18, 1969
Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-169-04805-80-00

Company - KREBBS & REESE

Farm - Pearson

No. 1

SEC. 33 T. 16 R. 3W
NW NW NW

Total Depth. 3370'

Comm. 9-1-59

Comp. 9-13-59


Shot or Treated.

Contractor. Melland Drlg. Co.

Issued. 11-28-59

County Saline

KANSAS



CASING:

8 5/8" 354' cem w/254 sx.

5 1/2" 3363' cem w/50 sx.

Elevation. 1349' RB

Production. 25 BOPD

Figures indicate Bottom of Formations.

surface soil & shale	40
sand	70
shale w/shells	354
lime	430
lime & gypsum	630
sandy lime	725
lime w/shale	860
shale w/shells	925
shale & shells	1400
shale & lime	1530
shale w/shells	1690
lime w/shale	1880
lime	1990
lime & shale	2060
shale & lime	2275
lime & shale	2335
shale & lime	2385
lime	2460
lime & shale	2515
shale & lime	2915
lime	2941
Mississippi lime	3113
lime & shale	3146
shale	3364
lime	3370 RTD
Total Depth	

TOPS: SCOUT

Mississippi	2914
Kinderhook	3127
Maquoketa	3363

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1968
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1968
CONSERVATION DIVISION
Wichita, Kansas