

API NUMBER ¹⁵ 169-20-294-60-00

LEASE NAME Ebling

WELL NUMBER 1

1080 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 33 TWP. 16 RGE. 3 W(E) or (W)

COUNTY Saline Co

Date Well Completed 7-12-87

Plugging Commenced 8-23-2000

Plugging Completed 8-24-2000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Excalibur Prod. Co. Inc.

ADDRESS 1016 N Main P.O. Box 278

PHONE (316) 241 1265 OPERATORS LICENSE NO. 5330

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ Location _____ (date)

by Max Tittel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Sent in with plugging application

Producing Formation Maquoketa Depth to Top 3332 Bottom 3334 T.O. 3419

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	328	8 5/8		NOTE
		0	3419	5 1/2		1650

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Fill with sand to 3300 ft spot cement with bailor five sack on sand

Rip pipe off at 1650 ft pull pipe out

Run 2 3/8 tubing to 400 ft hole was full of mud circulate cement from 400 to surface.

Name of Plugging Contractor Sunflower Well Service License No. 30280 RECEIVED

Address Box 341 Canton, Kansas STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Excalibur Prod. Co. Inc. OCT 3 2000

STATE OF Kansas COUNTY OF McPherson, ss. CONSERVATION DIVISION

Dennis D Gordley (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dennis D Gordley

(Address) P.O. Box 278 McPherson KS



SUBSCRIBED AND SWORN TO before me this 2nd day of October, 2000

Juanita M. Flood Notary Public

My Commission Expires: 5/27/04

USE ONLY ONE SIDE OF EACH FORM

