

15-169-00611-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Saline County. Sec. 32 Twp 16 Rge. 3 (E) x (W)  
Location as "NE/CNW&SW" or footage from lines: 1/2 1/2 1/2 1/2  
Lease Owner Frank J. Black  
Lease Name Holm Well No. 111  
Office Address Box 150 McPherson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 10-21-71 19  
Plugging completed 10-23-71 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Gilbert Moran  
Producing formation Depth to top Bottom Total Depth of Well 3377 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3381'	2805.53'
				8 5/8"	375'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mode bottom hole plug back with sand to 3370'. Mixed and ran 5 sacks cement thru churn bailer.  
Lugged hole to 300', set 25' rock bridge. Filled hole with 4 yards ready-mix from 275' to base of collar.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer  
Box 364 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 3 day of November, 1971.

My commission expires October 1972

Sidney D. Miller  
Notary Public.

W E L L R E C O R D

15-169-00611-00-00

LEASE: Holm

WELL NO. 4

LOCATION: N/2 NE/4 NW/4  
Section 32-16S-3W  
Saline County, Kansas

COMMENCED: July 24, 1960

COMPLETED: August 1, 1960  
(rotary)

OPERATOR: Warner & Stevenson  
728 East Kansas  
McPherson, Kansas

CONTRACTOR: Melland Drilling Company, Inc.  
1111 North Main Street  
Hutchinson, Kansas

CASING RECORD: 8-5/8" OD casing set at 375' with 178 sacks of cement.  
5-1/2" OD casing set at 3352' with 60 sacks of cement.

FORMATION

LOG

Surface soil, Red Bed & shale	100
Gypsum & shale	375
Anhydrite	470
Shale, shells & lime	640
Lime & shale	1200
Shale w/ lime	1535
Shale & shells	1780
Lime & shale	2650
Shale & lime	2800
Shale	2925
Shale & lime	2930
Mississippi Lime	3150
Shale	3387

ROTARY TOTAL DEPTH

RECEIVED  
GEOLOGICAL DIVISION  
AUG 17 1960  
GEOLOGICAL DIVISION  
Hutchinson, Kansas