

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dane G. Hansen Trust
Complete Address Box 187 Logan, Kansas 67646
Lease Name Cline Well No. 1
Location NW NW NW Sec. 12 Twp. 16 Rge. (E) (W) 25
County Ness Total Depth 4480'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Southwest Casing Pulling
Address Box 364 Great Bend, Kansas License No. 399
Operation Completed: Hour 12:30 P Day 30 Month 10 Year 1972

The above well was plugged as follows:

Total Depth 4480' 8 5/8 csg set at 294' cwc
5 1/2 csg set at 4475' cw 100 sk cmt.
Filled 5 1/2 csg W/sd (4460-4480) Dumped 5 sk cmt W/dump bailer. (4435-4460)
Cutoff and recovered 2860' of 5 1/2 csg.
Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls - 70 sk cmt - 10 sk
gel & water - released 8 5/8 plug and pumped 70 sk cmt by HOWCO.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Z. Massey
Well Plugging Supervisor

DATE 11/1/72
INV. NO. 6562-W