

15-135-20584-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc.
Complete Address Box 97 Ellinwood, Kansas 67526
Lease Name Sargent Well No. 1
Location SW NE NW Sec. 13 Twp. 16 Rge. (E) (W) 25
County Ness Total Depth 4525'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Co.
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 10:30 A Day 16 Month 6 Year 1972

The above well was plugged as follows:

Total Depth 4525' 8 5/8 csg set at 340' cwc: Cmt. Mat. 50-50 poz cmt W/64 total gel.
5 1/2 csg set at 4512' cw 100 sk cmt.
Filled 5 1/2 csg W/sd (4500-4525) dumped 5 sk cmt W/dump bailer. (4465-4500)
Cutoff and recovered 3200' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, 70 sk cmt, 12 sk
gel & water, released plug and pumped 70 sk cmt by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6/20/72
INV. NO. 5904-W