

KANSAS

Y  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

Aug 21 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Vincent Oil Corporation

Complete Address 719 Union Center Building Wichita, Kansas

Lease Name Huxman Well No. 1

Location C E/2 NE Sec. 15 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4543'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drilling

Address Wichita, Kansas License No.       

Operation Completed: Hour 8 A Day 19 Month 8 Year 1972

The above well was plugged as follows:

RTD 4543' 8 5/8 csg set at 276' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 60 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/21/72

INV. NO. 6198-W