

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1972
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling & Petroleum Resources
Complete Address Box 18407 Wichita, Kansas
Lease Name Evel "B" Well No. 1
Location SW NE Sec. 18 Twp. 16 Rge. (E) (W) 25
County Ness Total Depth 4484'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Heller Drilling
Address Wichita, Kansas License No.
Operation Completed: Hour 5 P Day 1 Month 1 Year 1971

The above well was plugged as follows:

RTD 4484' 8 5/8 csg set at 331' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 1-11-72
INV. NO. 4938-W