

*8*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. I23-34  
LOCATION EL NE NE  
SEC. 29 TWP. 26 RGE. 8E

Dry Hole \_\_\_\_\_ Abandoned Oil Well Yes Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 7 Lease \_\_\_\_\_ Drumm \_\_\_\_\_

Operator Saco Oil Co. Address El Dorado, Kansas

Field Blankenship County Butler

Total Depth 2668 Feet.

Plugging Contractor R. & D. Casin Pulling

Plugging Contractor's License No. 236

Address Ellinwood, Kansas

(Describe briefly the manner in which the well was plugged)

Filled with sand to 2595 ft. dumped 2 sacks cal seal, dumped 2 sacks  
cement on cal seal, dumped 2 more sacks cal seal, and 2 more sacks  
cement on cal seal.  
Mud to 250 ft.  
set 20 sacks cement on 10 ft. rock bridge @ 240 ft.  
Mud to 15 ft. set 5 sacks cement on 10 ft. rock bridge  
Filled to surface

STATE CORPORATION COMMISSION  
JUN 10 1955  
CONSERVATION DIVISION  
Wichita, Kansas

*Lawrence W. Matthews*  
District Conservation Agent

DATE June 6, 1955

**PLUGGING**  
FILE SEC. 29 TWP. 26 R. 8E  
BOOK PAGE 113 LINE 34