

15-169-2070-8000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

FORM CP-3
RECEIVED 1-8-82
STATE CORPORATION COMMISSION

APR 14 1982

API Number 15-169-20, Wichita, Kansas CONSERVATION DIVISION 170 ✓
-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Range Oil Co, Inc.

Complete Address 240 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name Nelson Well No. 1-A

Location C N/2 N/2 SW Sec. 15 Twp. 16 Rge. 3 (~~East~~) (West)

County Saline Total Depth 3558'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Operator and Allied Cementing Co.

Address _____ License No. _____

Operation Completed: Hour: 7:00 PM Day: 29 Month: March Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

Hole circulated and Filled with mud. 60 sacks cement pumped through drill pipe at 320'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.

Cement used 50/50 Pozzmic 4% gel 3% cc.

Order by Marián Schmidt.

Amount of Surface Casing: 8 5/8" (328') 275 sacks Common 7% cc.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was trying to stage cement into Pioneer Operations Co. Dalton S.W.D. SE/4 34-19-10W Rice Co. Too late when I got message.

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 4-16-82
INVOICE 9953-W