

15-169-00110-00-00

Form CP-3
Rev. 6-26-62

JF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1966
CONSERVATION DIVISION
TOPEKA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Specter Pipe & Supply, Inc.

Complete Address: P.O. Box 169, Russell, Kansas

Lease Name Swedlund Well No. 1

Location SE SE SW Sec. 15 Twp. 16 Rge. 3 (E) (W) X

County Saline Total Depth 3325'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Co. (Ralph Lynch)

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour Noon Day 11 Month March Year 1966

The Above well was plugged as follows:

Hole filled with sand to 3300' and cemented with 5 sacks.

Hole bailed to 210'. Rock bridge set from 210' to 200' and hole cemented with 20

sacks. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented

to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Ralph Lynch*
Well Plugging Supervisor

DATE 3/15/66
INV. NO. 2872-W