

15-101-20111-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 13 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Brandenburg Well No. C-1

Location CSE-NW Sec. 16 Twp. 16 Rge. (E) (W) 28

County Lane Total Depth 4438'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Slawson Drilling Company, Incorporated,

Address Above License No.       

Operation Completed: Hour 9:45 PM Day 8 Month 9 Year 1974

The above well was plugged as follows:

228'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 110 Cu. Ft. cement  
thru DP from 1050' to 725'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/4 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: K. L. D. Pihela  
Well Plugging Supervisor

INVOICED

DATE 9/13/74  
INV. NO. 9877-W