

15-101-20055 -00 -00

Form CP-3
Rev. 6-4-68

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,
Complete Address 617 Union Center Building, Wichita, Kansas.
Lease Name Lawrence Well No. 1
Location CNE-SE Sec. 16 Twp. 16 Rge. (E) (W) 28
County Lane Total Depth 4550'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 7:30 PM Day 25 Month 2 Year 1973

The above well was plugged as follows:

194'--8 5/8" Surface casing, cement circulated with 155 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement
thru DP from 900' to 575'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 2/28/73
INV. NO. 7066-44

Signed: A. G. Dickala
Well Plugging Supervisor