

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR MULL DRILLING COMPANY, INC.
 ADDRESS P.O. Box 2758
Wichita, KS 67201

API NO. 101-20,615-00-00
 COUNTY Lane
 FIELD Terwilliger East

**CONTACT PERSON Patricia L. Ungleich
 PHONE 264-6366

PROD. FORMATION P&A
 LEASE JAMES


PURCHASER NA
 ADDRESS _____

WELL NO. #1 'G'
 WELL LOCATION W/2 SW SW

DRILLING Blue Goose Drlg - Rig #1
 CONTRACTOR _____
 ADDRESS P.O. Box 1413
Great Bend, Kansas

660 Ft. from South Line and
255' Ft. from West Line of
 the SW/4 SEC. 31 TWP. 16S RGE. 28W

PLUGGING Blue Goose Drilling
 CONTRACTOR _____
 ADDRESS As above



TOTAL DEPTH 4593' RTD _____ PBTD _____
 SPUD DATE 2/17/82 DATE COMPLETED 2/26/82
 ELEV: GR 2785 DF _____ KB 2792

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS _____ (New) / (Used) casing.
CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	19.66#	344'	Commn	210 sx	3% cc, 2% gel

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

RECEIVED
 STATE CORPORATION COMMISSION
MAR 18 1982
 CONSERVATION DIVISION
 Wichita, Kansas

Date of first production <u>P&A 2/26/82</u>	Producing method (flowing, pumping, gas lift, etc.) <u>NA</u>	Gravity _____
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF
Disposition of gas (vented, used on lease or sold) <u>NA</u>	Water _____ %	Gas-oil ratio _____ CFPB
	Perforations <u>P&A</u>	

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.



Name of lowest fresh water producing stratum Unknown Depth

Estimated height of cement behind Surface Pipe Circulated

DV USED? NA

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
(See Attached Drillers Log)	SAMPLE TOPS			
	2193	+ 599	T/Anhydrite	
	2224	+ 568	B/Anhydrite	
	3961	-1169	Heebner	
	3978	-1186	Toronto	
	3997	-1205	Lansing	
	4333	-1541	B/Kansas City	
	4343	-1551	Marmaton	
	4445	-1653	Pawnee	
	4495	-1703	Ft Scott	
	4521	-1729	Cherokee	
	4570	-1778	B/Cher Lm	
	4584	-1792	Mississippi	
	4593	-1801	RTD	
DST #1 4279-4325/30-45-30-30 (Lans 'K' & 'L')				
First Open: 1½" decreasing to 1/2" in 30 min.				
Recovered: 100' muddy water (Chl= 15,000 ppm)				
ISIP 1014 IFP 47-47 FFP 62-62				
FSIP 998 IHP 2111 FHP 2111 122° F				
DST #2 4544-4573/30-45-60-60 (Lwr Cher Lm)				
Fair blow 3 inches in bubble bucket				
Recovered: 200' muddy water (Chl on bttm stand = 17,000 ppm)				
ISIP 1149 IFP 70-86 FFP 109-125 FSIP 1096				
P&A: 2/26/82 11:45 AM Plugging Agent: Paul Luthi				
2000'	50 sx			
900'	35 sx			
320'	35 sx (rubber plug)			
40'	10 sx (solid bridge/rubber plug)			
	10 sx in rathole	50-50 poz; 6% gel	2% cc	

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

Robert O. Wall OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,
 DEPOSES THAT HE IS President (~~KOR~~)(OF) MULL DRILLING COMPANY, INC.
 OPERATOR OF THE JAMES LEASE, AND IS DULY AUTHORIZED TO MAKE
 THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. #1 'G' ON
 SAID LEASE HAS BEEN COMPLETED AS OF THE 26th DAY OF February, 19 82, AND THAT
 ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.
 FURTHER AFFIANT SAITH NOT.

(S) Robert O. Wall
 Robert O. Wall, President
 SUBSCRIBED AND SWORN BEFORE ME THIS 12th DAY OF March 19 82

MY COMMISSION EXPIRES: March 27, 1983

