

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21, 478-00-00

LEASE NAME Roberts

WELL NUMBER D #1-5

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 5 TWP 16S RGE. 28W (E) or (W)

COUNTY Lane

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Da Mar Resources, Inc.

P.O. Box 70

ADDRESS Hays, KS 67601-0070

PHONE# (913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4425

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 5 1988
 CONSERVATION DIVISION
 WICHITA, KANSAS

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 345 | none |
| | | | | 5 1/2 | 4421 | 3195 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom with sand to 4380', bailed 5 sacks cement, shot @3630', 3412', 3195', plugged surface with 200 sacks 60/40 poz, 6% gel, 20 sacks gel, 400# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso


(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1988

Jane Hoover
 Notary Public

My Commission Expires:





15-101-21478-00-00

WHITE

ANDELLISDRILLING, Inc.

DRILLERS LOG

OPERATOR: DaMar Resources, Inc., P. O. Box 70, Hays, KS 67601

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Roberts "D" Well No. 1

Sec. 5 T. 16 S R. 28 W Spot NE SW NE

County Lane State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 345' with 175 sx. 2% Gel 3% CC

Production: 5 1/2" @ 4421' with 155 sx.

Type Well: Oil Well Total Depth 4425'

Drilling Commenced 7-13-88 Drilling Completed 7-22-88

| Formation | From | To | Tops |
|-------------|------|------|------|
| Cellar | 0 | 7 | |
| Shale, Lime | 7 | 4425 | |

RECEIVED
STATE CORPORATION COMMISSION

28 1988

CONSERVATION DIVISION
Wichita, Kansas

X