

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20.961-00

LEASE NAME James 'B'

WELL NUMBER 1-5

SPOT LOCATION SW SW NW

SEC. 5 TWP. 16S RGE. 28 or (W)

COUNTY Lane

Date Well Completed 4-19-84

Plugging Commenced 7:15 AM

Plugging Completed 10:00 A.M.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TEXAS-El Dorado Oil Co.

ADDRESS 550 West Central, Suite 1108
Wichita, Kansas 67203

PHONE # (316) 263-6853 OPERATORS LICENSE NO. 7245

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #1, Dodge City (Steve Durrant)

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 4500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand & Shale</u>		<u>0</u>	<u>297</u>	<u>8-5/8</u>	<u>289.53</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug @2040w/50 sx, plug @1260 w/50 sx, Plug @660 w/50 sx, Plug @330 w/40 sx;
Plug @40' with solid bridge/10 sx, 10 sx in rat hole. 210 sx 60/40
Pozmix, 2% Gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor D N B DRILLING, INC. License No. 5476

Address 535 North Oliver, Wichita, Kansas 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

James L. Donelson

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James L. Donelson

(Address) 535 North Oliver

SUBSCRIBED AND SWORN TO before me this 25 day of Apr, 1984

ELLA PRIESS


Notary Public

Ella Priess

My Commission expires: September 10, 1984

15-101-20961-00-00

D N B Drilling, Inc.



J. L. DONELSON, PRES.
(316) 687-5471

ROTARY CONTRACTOR DRILLING DEALS

535 NORTH OLIVER

WICHITA, KANSAS 67208

DRILLERS' LOG

Texas-ElDorado Oil Co.
550 W. Central, Suite 1108
Wichita, Kansas 67203

James 'B' #1-5
SW SW NW, Sec. 5-16S-28W
Lane County, Kansas

Commenced: 4-10-84
Completed: 4-19-84

Surface Casing: 8 joints 8-5/8" 23#
new, tallied 289.53, set @297,
cemented w/200 sx 60-40 Pozmix, 2% Gel,
3% cc. Plug down 8:30 P.M. 4-10-84.

FORMATION

DEPTH

Sand & Shale	0 - 297
Shale & Sand	297 - 1105
Sand & Shale	1105 - 2020
Anhydrite	2020 - 2052
Shale	2052 - 2870
Shale & Lime	2870 - 3420
Lime & Shale	3420 - 3640
Lime	3640 - 4500 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1984
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 25th day of April, 1984.

Ella Priess
Ella Priess, Notary Public

My appointment expires:
September 10, 1984

