

API NUMBER 15-101-20,194-00-00

LEASE NAME Roberts

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 3 TWP. 16 RGE. 28 (NW) or (W)

COUNTY Lane

Date Well Completed 10/24/76

Plugging Commenced 1:15 P.M. 7/13/95

Plugging Completed 3:30 P.M. 7/13/95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 13, 1995 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4451

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	248'	None
				4 1/2	4450'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mixed 350# Hulls then 150# hulls with 20 sx slurry. Then displaced down with 60 Bbl. water. Pressured to 500#. Released 883' came back. Perforated at 1300'. Pumped 140 sx down casing 400#. 100# Shut in. Pumped 150 sx down back side 400# pressure. 100# Shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales, Jr. (Employee of Operator) or (operator) of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Dane G. Bales, Jr.

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 17 day of July, 19 95



Betty Jane Bittel Notary Public

My Commission Expires: July 17, 1996

KANSAS DRILLERS LOG


API No. 15 — 101 — 20,194-00-00
 County Number

S. 3 T. 16S R. 28 E
 W

Loc. SE SE

County LANE

640 Acres
 N



Locate well correctly

Elev.: Gr. 2570

DF 2572 KB 2575 KB

Operator
DANE G HANSEN TRUST

Address
P O BOX 187, LOGAN, KANSAS 67646

Well No. 1 Lease Name **ROBERTS**

Footage Location
 660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor **C-G DRILLING CO.** Geologist **JEROLD E. JESPERSEN**

Spud Date **OCTOBER 12, 1976** Total Depth **4451** P.B.T.D. **4100**

Date Completed **OCTOBER 25, 1976** Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
SURFACE	12 1/4"	8 5/8"	28#	248.47'	COMMON	140	2% GEL 3% CA CL
PRODUCTION		5 1/2"	10.5#	4450'	10% SALT SAT	200	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			4	DP Jets	4005-8
			4	DP Jets	4020-3
			4	DP Jets	4056-9
			4	DP Jets	4294-7
			4	DP Jets	4402-5

TUBING RECORD

Size	Setting depth	Packer set at
2"	4095	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2750 gal. 15% Hel, 750 Mud	4004-7 & 4020-3
500 gal. Hel 15%	4056-9
1000 gal. Super X, 250 gal. Mud & 250 gal. 15% Hel	4294-7
	JUL 1 1995

INITIAL PRODUCTION

Date of first production 12/14/76 Producing method (flowing, pumping, gas lift, etc.) **Pumping**

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	<u>35</u> bbls.	<u>XX</u> MCF	<u>6%</u> bbls.	<u>XX</u> CFPB

Disposition of gas (vented, used on lease or sold) **vented** Producing interval (s) **Perfs. in 3 zones**

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
C-G DRILLING CO. DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
OIL

Well No. 1 Lease Name
ROBERTS

S 3 T 168 28^E W EST

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SHALE & SAND	0	1965	Anhydrite	1991
ANHYDRITE	1965	1980	Topeka	3471
SHALE	1980	3115	Heebner	3754
LIME & SHALE	3115	3890	Toronto	3774
LIME	3890	4398	Lansing	3792
MISSISSIPPI LIME	4398	4451	Stark Sh.	4041
RTD		4451	BKC	4108
DST #1 MISRUN			Marmaton	4125
DST #2 4000'-4060' 30-30-60-30 FAIR BLOW THRUOUT. REC 20' MUD 60' VSO&GCM 60' SO & GCM, 120' OGCM, 120' HO&GCM, 120'VHO&GCM (500' FLUID)			Pawnee	4211
IBHP 1181, FBHP 1158, IFP 161, FFP 275			Fort Scott	4293
DST #3 4108'-4146' 30-30-30-30 REC 5' MUD IBHP FAILED FBHP 46 IFP 34 FFP 34			Cherokee	4317
DST #4 4292'-4325' 30-30-30-30 REC 510' GIP 30' OCM 120' HO&GCWM 60' OCMW			Chreokee Sd.	4379
IBHP 683 FBHP 401 IFP 46 FFP 115			Mississippi	4400
			LTD	4454

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p style="text-align: right;"><i>Phyllis Buchanan</i> _____ Signature</p> <p style="text-align: center;">Phyllis Buchanan OFFICE Manager _____ Title</p> <p style="text-align: center;">October 29, 1976 _____ Date</p>
---------------	---