

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,687-00-00

LEASE NAME Shields Townsite

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

865 Ft. from S Section Line

990 Ft. from ^W Section Line

SEC. 32 TWP. 16 RGE. 28 ~~OR~~ (W)

COUNTY Lane

Date Well Completed 10-7-94

Plugging Commenced 10-7-94

Plugging Completed 10-7-94

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS BOX 352, Russell, KS. 67665

PHONE#(913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-7-94 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,615'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	262'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 50 sax cement @2,190' thru drill pipe. Spot 80 sax cement @1,410' thru drill pipe. Spot 40 sax cement @720' thru drill pipe. Spot 40 sax cement @290' thru drill pipe. Dump 10 sax cement @40'. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Plugging complete @10AM.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Shields Drilling Co.) (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 94

My Commission Expires: _____



Notary Public

RECEIVED
OCT 20 1994
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS



Shields


15-101-21687-00-00

Russell, Kansas

WELL LOG

Operator: John O. Farmer, Inc.
 Well: Shields Townsite #1
 Commenced: September 27, 1994
 Completed: October 7, 1994
 Contractor: Shields Drilling Co.

Well Description: Approx. NE SW SW
 Sec. 32-16S-28W
 Lane Co., Kansas



Elevation: 2,786' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	262'	Cmtd. w/175 sax

..... Figures Indicate Bottom of Formations

Sand & shale	2,182'	
Anhydrite	2,213'	
Shale & sand	2,681'	
Shale	2,855'	
Shale & lime	3,822'	
Lime	4,615'	RTD

Notes

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 20 1994
 CONSERVATION DIVISION
 WICHITA, KANSAS