

15-101-20487-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas. 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Lane SEC. 30 TWP. 16 RGE. 28W E/W
Location as in quarters or footage from lines:
NW NW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Liberty Enterprises, Inc.
Lease Name James #1 Well No. _____
Office Address 308 West Mill Street, Plainville, Kansas 67663
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6-7-83
Plugging completed 6-17-83
Reason for abandonment of well or producing formation _____

_____ Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom _____ T.D. 4595'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	278'	none
				4-1/2"	4594'	897'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 4500' and ran 4 sacks cement. Shot casing @3510',
3030', 2505', 1505', 900' and pulled a total of 23 joints of 4-1/2" casing.
Plugged well with 3 hulls, 15 gel, 70 cement, 20 gel, 1 hull, released plug and
displaced with 125 cement.
Plugging Complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 83

My Commission expires:  [Signature]
Notary Public.

7-20-83

FILE COPY

KANSAS DRILLERS LOG


API No. 15 — 101 — 20487-00-00
County Number

S. 30 T. 16 R. 28 ^{NE}_W

Loc. NW NW SW

County Lane

640 Acres



Locate well correctly

Elev.: Cr. 2789

DF 2791 KB 2794

Operator Liberty Enterprises, Inc.

Address 308 West Mill Plainville, Kansas 67663

Well No. #1 Lease Name James

Footage Location
2310 feet from SE (S) line 330 feet from CD (W) line

Principal Contractor Pioneer Drilling Company Geologist Robert Pfannenstiel

Spud Date 10-22-80 Total Depth 4595 P.B.T.D. 4565

Date Completed 11-1-80 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/2"	8 5/8"	28#	278	common	140	2% gel, 3% cc
production	7 7/8"	4 1/2"	10 1/2#	4594	common	200	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4		4543-45
TUBING RECORD			4		4548-52
Size	Setting depth	Packer set at	4		4556-58
2"					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gallon mud acid	4543-58
1500 gallon I.N.S. acid	4543-58

INITIAL PRODUCTION

Date of first production _____ Producing method (Flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Geological Survey of Kansas, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please call 316-522-2206. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas.

COPY

Operator
Liberty Enterprises, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.
#1

Lease Name
James

OIL

S 30 T 16 R 28 ^{EC} W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>Geological & Completion Report Enclosed</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received


 Robert F. Pfannenstiel Signature
 Petroleum Geologist Title
 March 5th, 1981 Date