


15-101-20244-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Lane \_\_\_\_\_ County. Sec. 30 Twp. 16 Rge. 28 NE/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines \_\_\_\_\_  
N/2, NE, SW  
Lease Owner Petroleum, Inc.  
Lease Name James "C" Well No. 1  
Office Address P. O. Box 1447, Great Bend, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Flat

Oil  
Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced June 4 1979  
Plugging completed June 14 1979  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4600'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	283'	NONE
				5 1/2"	4598	1223.45'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped sand to 4300' with five (5) sacks cement  
Shot casing at 3500'  
Spotted 100 bbls oil behind casing  
Shot casing at 3000', 2500', 2000', 1800', 1400', 1200'  
Pulled 30 joints of 5 1/2" Scotchkote casing  
Squeezed well with three (3) sacks hulls, 70 sacks 50/50 pozmix cement, (6) six sacks gel and 60 sacks cement


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
James W. Rockhold Box 698 Gt Bend, KS  
(Address) \_\_\_\_\_ 67530

SUBSCRIBED AND SWORN TO before me this 19th day of June, 1979



My commission expires \_\_\_\_\_

Cathy L. Cole  
Notary Public.

DRILLERS LOG

15-101-20244-00-00

OPERATOR: Petroleum, Inc.  
P. O. Box 1447  
Great Bend, Kansas 67530

LEASE: James 'C' No. 1  
N/2 NE SW Sec. 30-16S-28W  
Lane County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 One Twenty Building  
Wichita, Kansas 67202

COMMENCED: 8-16-77

COMPLETED: 8/28/77

RTD: 4600'

CASING: 8-5/8" set at 283' with 225 sx cement

OIL STRING: 5-1/2" set at 4598' with 125 sx cement

0' to 287' 12 1/2" surface hole & shale & sand  
287' to 317' Shale  
317' to 2186' Shale & Shells  
2186' to 2215' Anhydrite  
2215' to 2835' Shale & Shells  
2835' to 3056' Shale & Lime  
3056' to 3405' Lime & Shale  
3405' to 3590' Shale & Lime  
3590' to 4140' Lime & Shale  
4140' to 4525' Lime  
4525' to 4600' Lime & Shale  
4600 RTD

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 2 1979  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg of the Slawson Drilling Company, Inc.  
hereby state that the above and foregoing is a true and accurate copy of the  
log for the James 'C' No. 1 well.

*James C. Remsberg*  
James C. Remsberg

Subscribed and sworn to me this 8th day of September, 1977.

*Mary Lou Taylor*  
Mary Lou Taylor, Notary

My commission expires January 17, 1981

