

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 5 101-21,212-00-00

LEASE NAME Tillotson

WELL NUMBER #1-29

990' Ft. from S Section Line

3360' Ft. from E Section Line

SEC. 29 TWP. 16s RGE. 28 (E) or (W)

COUNTY Lane

Date Well Completed 9-13-85

Plugging Commenced 9-13-85

Plugging Completed 9-13-85

LEASE OPERATOR Roger L. Martin

ADDRESS PO Box 47610 Wichita, KS 67201

PHONE# (316) 682-0038 OPERATORS LICENSE NO. KCC#4169

Character of Well D+A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? CL

Producing Formation na Depth to Top na Bottom na T.D. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surface Casing</u>	<u>SH</u>			<u>8 1/2"</u>	<u>376'</u>	<u>NA</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged with 235 sacks of 60-40 Pozmix, 6% gel.

50 sks @ 2200', 50 sks @ 1340', 50 sks @ 1000', 50 sks @ 400', solid bridge plug @ 40' w/10 sks, 15 sks in R.H. 10 sks in M.H.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard Drilling Company License No. KCC#5651

Address 412 East Douglas, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Roger L. Martin (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 47610 Wichita, KS 67201

Subscribed and sworn to before me this 1<sup>st</sup> day of October, 19 85

[Signature]  
Notary Public

RECEIVED

STATE CORPORATION COMMISSION

OCT 8 1985

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires: August 10, 1988

J.A. Martin  
NOTARY PUBLIC  
State of Kansas  
MY APPT. EXPIRES 8-10-88

Form CP-4  
Revised 08-84

15-101-21212-00-00

DRILLERS' LOG

COMPANY: Roger L. Martin  
CONTRACTOR: Mallard Drilling  
P. O. Box 905  
McPherson, Kansas 67460

WELL NAME: Tillotson #1-29  
DESCRIPTION: NW SE SW  
Sec. 29-16S-28W

RIG NO: 1  
TOTAL DEPTH: 4660'  
COMMENCED: September 3, 1985  
CASING RECORD: 8 joints, 8 5/8" x  
23# casing

COUNTY: Lane  
ELEVATION: 2787 K.B.  
COMPLETED: September 13, 1985

\*\*\*\*\*

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	
Soil, shale	0	716	Ran 8 jts. new 8 5/8" x
Shale, sand	716	1770	23# casing set @ 346'.
Sand	1770	1970	Cemented w/ 200 sx. 60/40
Shale	1970	2194	poz., 3% cc., 2% gel. CDC
Anhydrite	2194	2227	PD @ 1:45 a.m. 9-4-85.
Shale	2227	2508	
Shale, lime	2508	3074	Ran 4 DST's.
Shale	3074	3277	
Lime, shale	3277	3447	Ran 1 Electric Log
Shale	3447	3737	
Lime, shale	3737	4104	Plugged hole w/ 235 sx.
Lime	4100	4405	60/40 poz., 6% gel as follows
Marmaton	4405	4524	
Cherokee	4524	4590	1st plug @ 2200' w/ 50 sx.
Mississippi	4590	4660	T.D. 2nd plug @ 1340' w/ 50 sx. 3rd plug @ 1000' w/ 50 sx. 4th plug @ 400' w/ 50 sx. 5th plug @ 40' S.B.P. w/ 10 sx. rathole w/ 15 sx., mousehole w/ 10 sx. P.D. @ 7:30 a.m. 9-13-85

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF McPHERSON)

I, BRYAN HESS of MALLARD DRILLING, certify that this is a true and correct copy of the log of the Tillotson #1-29 well to the best of my knowledge.

Bryan Hess  
Bryan Hess  
General Manager

Subscribed and sworn to before me this 1st day of Nov., 1985.

My appointment expires:

Gladys I. Huber  
Notary Public

