

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-20,548-00-0

LEASE NAME Demand

WELL NUMBER #25-22

SPOT LOCATION NW NW NE

SEC. 25 TWP. 16 S. RGE. 28 (E) or (W)

COUNTY Lane

Date Well Completed 8-10-81

Plugging Commenced 4-22-85

Plugging Completed 4-25-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Oxford Exploration Co.

ADDRESS 1550 Denver Club Building
Denver, CO 80202

PHONE # (303) 572-3821 OPERATORS LICENSE NO. 6889

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #1 302 West McArtor Dodge City, KS 67801

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Cherokee Depth to top 4586 bottom 4594 T.D. 4660

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From surface	To	Size	Put in	Pulled out
		361	4659	8 5/8	361	see attached
				4 1/2	4659	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

See attached.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Plains, Inc. License No. _____
 Address Ness City, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF _____ COUNTY OF _____ MAY 09 1985

David E. Park (employee of CONSERVATION DIVISION)
 (operator) of above-described well, being first duly sworn on oath, Wichita, Kansas
 I have knowledge of the facts, statements, and matters herein contained and
 the log of the above-described well as filed that the same are true and
 correct, so help me God.

(Signature) David E. Park

(Address) 1550 Denver Club Bldg.
Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 7th day of MAY, 1985

Jeri S. Haney
 Notary Public

My Commission expires: 4-19-88

15-101-20548-00-00

DEMAND # 25-22

- H-22 filled with sand up to 4500'
- H-23 Ran Bailer to check sand top @ 4500'
 worked pipe and shot off @ 2174' could not pull pipe
 Rig up and shot off @ 1600' work pipe could not pull
 Rig up and shot off @ 772' start cut hole with pipe call state plugger lay casing out shut down & Release Rig
- H-24 State plugger wanted to go in hole with tubing & packer & try to go back in 4 1/2" with packer
 Ran packer to 1385' could not get deeper shut down
- H-25 Rig up Halco pump truck wash out sand & mud to 1475'. Pumped 50 sk plug in casing
 Pulled packer up to 1200' set packer to psi up to 500[#] psi. shut in 1 hr. Release psi. Rig up
 Tools went in hole with gun tag cement top @ 1286' shot 4 holes @ 1280'
 Rig up Halco & squeeze with 125 sk baropos with 3% C.C. Release packer & put 10 sk plug @ perf.
 Pull tubing to 740' mix 5 sks. Gel & 2 sk. Sull.
 Pump down hole follow with 20 sk plug

RECEIVED
 STATE CORPORATION COMMISSION

MAY 09 1985

Pull Tubing up to 410' mix & pump 40 lbs
60/40 pore 3% c.c. To plug 40' below & 40' in
surface pipe. pull all tubing out 1 ft. mix
& pump 15 lbs cement top of surface 60/40 pore
3% c.c.

State happy