


15-101-20237-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Lane _____ County. Sec. 25 Twp. 16 Rge. 28 E/W
Location as "NE/CNW/SW" or footage from lines _____
C E/2 NW NE
Lease Owner Braden & Deem
Lease Name _____ Demand #1 _____ Well No. _____
Office Address Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/25/79 _____ 19____
Plugging completed 6/28/79 _____ 19____
Reason for abandonment of well or producing formation
depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4660
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	309	none
				4 1/2"	4659	1026

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pushed wood plug to 4350' and sanded to 4300', ran 4 sacks cement. Loaded hole with
salt water, shot pipe at 3502', 3005', 2013', 1504', 1030', pulled 34 joints. Allied
pumped 3 sacks hulls, 70 sacks cement, 7 sacks gel, plug and 60 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 79

My commission expires _____


Margaret Melcher
Notary Public.

CONTRACTOR'S WELL LOG

15-101-20237-00-00

OPERATOR:
CONTRACTOR:
WELL NAME
LOCATION:

SPUD DATE:
COMPLETION DATE:

Rockwood Petroleum Company
Abercrombie Drilling, Inc.
Demand #1
C E/2 NW NE Section 25-16S-28W
Lane County, Kansas
August 8, 1977
August 19, 1977

0	312	Sand & clay
312	775	Shale & sand
775	900	Sand
900	1050	Shale
1050	1507	Sand & shale
1507	2124	Shale & sand
2124	2166	Shale
2166	2202	Anhydrite
2202	2893	Shale
2893	3211	Lime & shale
3211	3792	Shale & lime
3792	3961	Lime & shale
3961	4104	Lime
4104	4187	Shale & lime
4187	4260	Lime
4260	4435	Lime & shale
4435	4540	Lime
4540	4610	Lime & shale
4610	4660	Lime
	4660	Rotary Total Depth

Spud hole at 7:30 p.m., August 8, 1977. Drilled 312' of 12 1/4" hole. Set at 308.81' K.B. Cemented with 200 sacks cement, 2% gel, 3% CaCl. Plug was down at 2:45 a.m., August 9, 1977.

R.T.D. 4660'. Ran 146 joints of 4 1/2" - 10 1/2# 8 rd thd casing. Set at 4659'. Cemented with 500 gal. chemical flush, followed with 200 sacks of 60/40 posmix, 10% salt, 2% gel, 3/4 of 1% CFR-2, 6# of gilsonite per sack. Plug was down at 11:20 p.m., August 19, 1977.

SAMPLE TOPS:

Anhydrite	2166' (+587)	Lansing	4008' (-1255)
B/Anhydrite	2202' (+551)	B/KC	4336' (-1583)
Heebner	3971' (-1218)	Marmaton	4381' (-1628)
Toronto	3990' (-1237)	Pawnee	4409' (-1656)

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION


MAY 17 1979

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Demand #1, C E/2 NW NE Section 25-16S-28W, Lane County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge
Jack L. Partridge, Ass't. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 24th day of August, 1977.



Sandra Richman
Sandra Richman, Notary Public

My commission expires July 21, 1979.