



KANSAS CORPORATION COMMISSION 1076786
OIL & GAS CONSERVATION DIVISION

Form ACO-1
June 2009
Form Must Be Typed
Form must be Signed
All blanks must be Filled

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 34592
Name: Kansas Resource Exploration & Development, LLC
Address 1: 9393 W 110TH ST, STE 500
Address 2: _____
City: OVERLAND PARK State: KS Zip: 66210 + _____
Contact Person: Bradley Kramer
Phone: (913) 669-2253
CONTRACTOR: License # 8509
Name: Evans Energy Development, Inc.
Wellsite Geologist: N/A
Purchaser: Coffeyville Resources

Designate Type of Completion:

- New Well Re-Entry Workover
- Oil WSW SWD SIOW
 Gas D&A ENHR SIGW
 OG GSW Temp. Abd.
 CM (Coal Bed Methane)
 Cathodic Other (Core, Expl., etc.): _____

If Workover/Re-entry: Old Well Info as follows:

Operator: _____

Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____

- Deepening Re-perf. Conv. to ENHR Conv. to SWD
 Conv. to GSW
- Plug Back: _____ Plug Back Total Depth _____
 Commingled Permit #: _____
 Dual Completion Permit #: _____
 SWD Permit #: _____
 ENHR Permit #: _____
 GSW Permit #: _____

<u>01/13/2012</u>	<u>01/17/2012</u>	<u>01/23/2012</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 15-091-23745-00-00

Spot Description: _____

NE SW SW NE Sec. 15 Twp. 14 S. R. 22 East West

3171 Feet from North / South Line of Section

2063 Feet from East / West Line of Section

Footages Calculated from Nearest Outside Section Corner:

- NE NW SE SW

County: Johnson

Lease Name: KNABE M Well #: KR-10

Field Name: Gardner

Producing Formation: Bartlesville

Elevation: Ground: 981 Kelly Bushing: 0000

Total Depth: 850 Plug Back Total Depth: 840

Amount of Surface Pipe Set and Cemented at: 20 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set: _____ Feet

If Alternate II completion, cement circulated from: 840

feet depth to: 0 w/ 125 sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content: 000000 ppm Fluid volume: 150 bbls

Dewatering method used: Evaporated

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: _____ License #: _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West

County: _____ Permit #: _____

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Submitted Electronically

KCC Office Use ONLY

- Letter of Confidentiality Received
Date: _____
- Confidential Release Date: _____
- Wireline Log Received
- Geologist Report Received
- UIC Distribution
- ALT I II III Approved by: Deanna Garrison Date: 03/23/2012



1076786

Operator Name: Kansas Resource Exploration & Development, LLC Lease Name: KNABE M Well #: KR-10

Sec. 15 Twp. 14 S. R. 22 East West County: Johnson

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Electric Log Submitted Electronically <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(If no, Submit Copy)</i> List All E. Logs Run: Gamma Ray Neutron CCL	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%;">Name</td> <td style="width:20%;">Top</td> <td style="width:20%;">Datum</td> </tr> <tr> <td>Bartlesville</td> <td>792'</td> <td>189'</td> </tr> </table>	Name	Top	Datum	Bartlesville	792'	189'
Name	Top	Datum					
Bartlesville	792'	189'					

CASING RECORD <input type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	9.8975	7	14	20	Portland	6	
Production	5.625	2.875	6.5	840	50/50 Poz	125	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing	-			
___ Plug Back TD				
___ Plug Off Zone	-			

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
2	792.0' - 802.0' 21 Perfs	2" DML RTG	792.0' - 802.0'

TUBING RECORD:	Size: <u>1"</u>	Set At: <u>820'</u>	Packer At: <u>N/A</u>	Liner Run: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or ENHR.		Producing Method: <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) _____		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Duaily Comp. <input type="checkbox"/> Commingled <i>(Submit ACO-5)</i> <i>(Submit ACO-4)</i> <input type="checkbox"/> Other (Specify) _____	PRODUCTION INTERVAL: _____ _____
---	--	--



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER, 36766

LOCATION Ottawa, KS

FOREMAN Carey Kennedy

PO Box 884, Chanute, KS 66720
820-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11/7/12	4448	Knabe M KR-10	NE 15	14	22	JO
CUSTOMER <u>Kansas Resources Exp + Dev</u>			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS <u>9393 W. 110th St, Suite 500</u>			<u>481</u>	<u>Coker</u>	<u>CK</u>	
CITY STATE ZIP CODE <u>Ovland Park KS 66210</u>			<u>485</u>	<u>Ala Mea</u>	<u>AM</u>	
			<u>570</u>	<u>Der Mes</u>	<u>DM</u>	
			<u>369</u>	<u>Art McD</u>	<u>ADM</u>	

JOB TYPE logstring HOLE SIZE 5 7/8" HOLE DEPTH 850' CASING SIZE & WEIGHT 2 7/8" EUG
 CASING DEPTH 840' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 2-2 1/2" rubber plug
 DISPLACEMENT 4.88 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 100# Premium Gel followed by 10 bbls fresh water, mixed & pumped 125 sks 50/50 Pozmix cement w/ 2% gel & 1/8" Phenoseal per sk, cement to surface, flushed pump clean, displaced 2 2 1/2" rubber plugs to casing TD w/ 4.88 bbls fresh water, pressured to 800 PSI, released pressure, shut in casing.

(Handwritten signature)

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE cement pump		1030.00
5406	on lease	MILEAGE pump truck		—
5402	840'	casing footage		—
5407	1/2 minimum	tax mileage		175.00
5502C	1.5 hrs	80 Vac		135.00
1124	125 sks	50/50 Pozmix cement		1368.75
1118B	310 #	Premium Gel		65.10
1107A	63 #	Phenoseal		81.27
4402	2	2 1/2" rubber plugs		56.00
			7.525%	SALES TAX
				ESTIMATED TOTAL
				<u>3029.35</u>

Rev'n 9737

AUTHORIZATION *(Signature)* TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.