

1080221

TO: STATE CORPORATION COMMISSION 10-12 API NUMBER 15-101-20,626 -00-00
NE NE SEC. 16, T 16 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 740 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME NIMOCKS-JOHNSON WELL # 4

TECHNICIAN'S PLUGGING REPORT COUNTY LANE 68.58

OPERATOR LICENSE # 31566 WELL TOTAL DEPTH 2110 FEET

OPERATOR: BENCHMARK OIL & GAS CORP PRODUCTION CSG: SIZE 4 1/2 " FEET 2109

NAME AND 1515 ARAPAHOE ST., STE 580 SURFACE CASING: SIZE 8 5/8" FEET 273'

ADDRESS DENVER, CO 80202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-20,776 D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR CHEYENNE DRILLING LICENSE NUMBER 7146

ADDRESS PO BOX 384, NESS CITY, KS 67560-0384

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 12 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM TERRY MAXWELL

(COMPANY NAME) CHEYENNE DRILLING (PHONE) 785-798-2282

WERE: PERFS AT 1776-1804, 1816-30 4 1/2" AT 2109' WITH 600 SX CEMENT

PUMP 200# HULLS DOWN 4 1/2" CASING, START CEMENT, MIX 200# HULLS IN FIRST 40 SX CEMENT.

PUMPED 125 SX CEMENT DOWN 4 1/2" CASING. MAXIMUM PSI PRESSURE AT 2000#. SHUT IN AT 900#.

PUMP 5 SX CEMENT DOWN 8 5/8" X 4 1/2" ANNULAS.

10-22-98

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 12 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT _____

PUMPED 200# HULLS DOWN 4 1/2" CASING, STARTED CEMENT, MIXED 200# HULLS IN FIRST 40 SX CEMENT

PUMPED 125 SX CEMENT DOWN 4 1/2". MAXIMUM PSI PRESSURE AT 2000#. SHUT IN AT 900#. PUMPED

5 SX CEMENT DOWN 8 5/8" X 4 1/2" ANNULAS. HOLE IN SURFACE PIPE HOLE DID STAY LOADED.

ON 10-13-98 CHECKED CEMENT TOP 30' DOWN. WILL TOP OFF.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

SIGNED Kevin D Strube
(TECHNICIAN) FORM CP-2/3

10-23-98
60170