

5-1 15-101-20038-00-00

1 070803

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 9/30/72

C SE NE, SEC. 16, T 16 S, R 28 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Nimocks Johnson Well # 1

Operator: Murfin Drilling Company

County Lane 147.06

Name & Address 250 North Water, Suite 300
Wichita, KS 67202

Well Total Depth 4525 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 161

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:45 p.m. Day: 23 Month: 4 Year: 19 90

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4523' PBTB 4500' Perfs at 3880-4401' (13 sets)

1st plug sand back to 3830' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 60 sx cement at 1100',

3rd plug pump 100 sx cement down surface pipe.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:55 a.m. Day: 1 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3820' and dumped 5 sx cement on top of sand

through bailer, 2nd plug shot and squeezed at 1100' with 5 sx gel and 80 sx cement

with 1/2# flo-seal per sx. 3rd plug shot at 550' and squeezed with 70 sx cement with 1/2#

flo-seal per sx. 5/1/90 4th plug pumped 100 lbs. hulls in first part of 100 sx cement

down 5 1/2". Maximum pressure 1000 psi and shut in 400 psi. 5th plug pumped 100 lbs. hulls

in first part of 100 sx cement down annulus. Maximum pressure 300 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Dan Loober (TECHNICIAN)

DATE 5-16-90

NOV. 28 1990 JUL 11 1990