

1080222

TO: STATE CORPORATION COMMISSION

10-12

API NUMBER 15-101-20,616-00-00
NE NE SEC. 16, T 16 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME NIMOCKS-JOHNSON WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE

OPERATOR LICENSE # 31566

WELL TOTAL DEPTH 4565 148.37 FEET

OPERATOR: BENCHMARK OIL & GAS CORP PRODUCTION CSG: SIZE 4 1/2 " FEET 4565

NAME AND ADDRESS 1515 ARAPAHOE ST., STE 580 SURFACE CASING: SIZE 8 5/8" FEET 290'

DENVER, CO 80202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CHEYENNE DRILLING LICENSE NUMBER 7146

ADDRESS PO BOX 384, NESS CITY, KS 67560-0384

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 12 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM TERRY MAXWELL

(COMPANY NAME) CHEYENNE DRILLING (PHONE) 785-798-2282

WERE: PERFS AT 3861-65, 4032-46, 4085-91, 4116-20, 4126-28, 4131-38 4 1/2" AT 4565' W/375 SX SET CIBP AT 2950'. PERFORATE AT 1350'. CIRCULATE CEMENT TO SURFACE.

10-22-98

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 12 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT LOG-TECH OF KS RAN GAUGE RING TO 3000'. SET CIBP AT 2950' WITH 2 SX CEMENT ON TOOP. PERFORATED AT 1350'. ALLIED PUMP DOWN 4 1/2" WITH WATER LOADED HOLE TOOK INJECTION RATE 3 1/2 BBL PER MINUTE 500#. STARTED CEMENT. PUMPED 150 SX, SHUT IN WELL ON VACUUM. WENT DOWN 8 5/8 X 4 1/2 PUMPED 58 SX. MAXIMUM PSI PRESSURE AT 800#. SHUT IN AT 475# WENT BACK DOWN 4 1/2 PUMPED 200# HULLS AND 77 SX CEMENT. WELL ON VACUUM SHUT IN. LET SET 2 HRS. TOPPED OFF WITH 15 SX CEMENT. HOLE STAYED LOADED.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

SIGNED Kevin D. Strube (TECHNICIAN) FORM CP-2/3

10-23-98
60171