

1 050174

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,145 - 00-01

C/SW SE, SEC. 14, T 16 S, R 28 W/EX

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7462

Lease Name Ruby Ryan Well # 1

Operator: Voyager Petroleums, Inc.

County Lane

Name & Address 800 Petroleum Bldg., 110 16th St.  
Denver, CO 80202

Well Total Depth 4475 145.44 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:00 pm Day: 12 Month: March Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2 set at 4455 Top Perfs 4294 - 99 PBDT 4396

1st plug Sand back from 4396 to 4200 with 18 sx sand and dump 5 sx cement on top of sand

2nd plug Pump in sequence 6 sx hulls, 20 sx gel, 75 sx cement, 20 sx gel, 1 sack hulls and release 8 5/8" rubber plug and pump additional 100 sx cement

Maximum pressure 500# and shut-in pressure 175#

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:45 pm Day: 12 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4455 Top Perfs 4294-99 PBDT 4396

1st plug Sand back from 4396 to 4200 with 18 sx sand and dump 5 sx cement on top of sand

2nd plug pump in sequence 6 sx hulls, 20 sx gel, 75 sx cement, 20 sx gel, 1 sack hulls and release 8 5/8" rubber plug and pump additional 100 sx cement

Maximum pressure 500# and shut-in pressure 175#

MAR 1 1984  
03-19-84

Remarks: Use 60/40 Pozmix 2% gel 3% cc. They recovered 1600' of 4 1/2" casing by Halliburton  
(if additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 3-21-84

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 0842