

1 050776

API NUMBER 15- 101-21,292 - 00-00

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE NW, SEC. 9, T 16 S, R 28 W
4290 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Walton Well # 1-B

Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Suite 205
Wichita, KS 67202

County Lane
Well Total Depth 4445 Mississippi, 4446 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 1 Month: March Year: 19 86

Plugging proposal received from Gary Christopher

(company name) Pickrell (phone) 316-262-8427
Elevation 2610

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2030-65'

1st plug at 2025' with 50 sx cement

2nd plug at 1500' with 80 sx cement

3rd plug at 350' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:15 pm Day: 1 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2065' with 50 sx cement, 2nd plug at 1500' with 80 sx
cement, 3rd plug at 330' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15
sx cement.

Remarks: Used 60/40 Pozmix 4% gel 2% cc by Allied.

(If additional description is necessary, use BACK of this form.)

I (xxx / did not) observe this plugging.

MAR 12 1986

STATE CORPORATION COMMISSION

MAR 11 1986

Signed

Richard W. Lacey
(TECHNICIAN)

WV. NO. 12953

CONSERVATION DIVISION
Wichita, KansasFORM CP-2/3
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 2 17 86
month day year

API Number 15- 101-21,292-00-00

OPERATOR: License # 5123
 Name Pickrell Drilling Company, Inc.
 Address 110 N. Market, Suite 205
 City/State/Zip Wichita, Kansas 67202
 Contact Person Jay McNeil
 Phone 262-8427

SW NE NW Sec. 29 Twp. 16 S. Rg. 28 East
 4290 West
 3630 Ft. from South Line of Section
 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5123
 Name Pickrell Drilling Company, Inc.
 City/State Wichita, Kansas

Well Drilled For: Well Class: Type Equipment:
☒ Oil ☐ SWD ☐ Infield ☒ Mud Rotary
☐ Gas ☐ Inj ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☐ Expl ☒ Wildcat ☐ Cable

If OWWO: old well info as follows:

Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing

Date 2-13-86 Signature of Operator or Agent Title Chief Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.

This Authorization Expires 2-13-86 Approved By 2-13-86

Set 300 of 8 5/8 on 2/19/86

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2025'	feet depth with 50	exs of 60/40 poz. 4%gel 2% CC
2nd plug @ 1500	feet depth with 80	exs of " "
3rd plug @ 350	feet depth with 50	exs of " "
4th plug @ 40' w/solid bridge	feet depth with 10	exs of " "
5th plug @ plug	feet depth with	exs of " "
(2) Rathole with 15	exs	(b) Mousehole with N/A

PUSHER Gary Christopher
 TD 4445 FORMATION MISS
 SURFACE PIPE 8 5/8 @ 304
 ANHYDRITE 2030 ELEVATION 2610
 STARTING TIME & DATE 2065 3-1-86
 COMPLETION TIME & DATE 3:15 PM
 1st PLUG @ 2065 FT. W/ 50 SX
 2nd PLUG @ 1500 FT. W/ 80 SX
 3rd PLUG @ 330 FT. W/ 50 SX
 4th PLUG @ 40-0 FT. W/ 10 SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ SX
 WATER WELL PLUGGED W/ SX
 CEMENT COMPANY ACCUED
 TECHNICIAN

STATE CORPORATION COMMISSION

MAR 11 1986

CONSERVATION DIVISION
Wichita, Kansas