

To: 1 330473
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE NE NW, SEC. 7, T 16 S, R 28 WY
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,296-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name &
Address 110 N. Market, Suite 205
Wichita, KS 67202

4290 feet from S section line
2970 feet from E section line
Lease Name Eaton Estate Well # 1-A
County Lane 140.95
Well Total Depth 4337 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Co., Inc. License Number 5123
Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 15 Month: March Year: 19 86

Plugging proposal received from Gary Christopher

(company name) Pickrell (phone) 316-262-8427
Elevation 2595'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2021'

1st plug at 1550' with 50 sx cement - tag plug

2nd plug at 1000' with 80 sx cement

3rd plug at 360' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 am Day: 15 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1525' with 50 sx cement - set 3 hours and tagged
cement at 1425, 2nd plug at 1000' with 80 sx cement, 3rd plug at 360' with 40 sx cement,
4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx
cement, 6th plug to circulate rat hole with 15 sx cement.

MAR 31 1986

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

I (XXX / did not) observe this plugging.

INVOICED

Signed Steve Durrant
(TECHNICIAN)

DATE APR 1 1986

INV NO 13214-3-15

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 3 4 86
month day yearAPI Number 15- 101-21,296-00-00
SE NE NW Sec. 7 Twp. 16 S, Rg. 28 X East
4290 Ft. from South Line of Section
2970 Ft. from East Line of SectionOPERATOR: License # 5123
Name Pickrell Drilling Company, Inc.
Address 110 N. Market, Suite 205
City/State/Zip Wichita, KS 67202
Contact Person Jay McNeil
Phone 262-8427(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County LaneLease Name Eaton Estate Well # 1-A
Ground surface elevation 2595 feet MSLDomestic well within 330 feet: yes X noMunicipal well within one mile: yes X no

Depth to bottom of fresh water 140 feet

Depth to bottom of usable water 1000 feet

Surface pipe by Alternate: 1 2 X

Surface pipe planned to be set 250' +

Conductor pipe required

Projected Total Depth 4500 feet

Formation Mississippi

CONTRACTOR: License # 5123
Name Pickrell Drilling Company, Inc.
City/State Wichita, KansasWell Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 2-25-86 Signature of Operator or Agent Page McNeil Title Chief Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. 402

This Authorization Expires 2-26-86 Approved By 2-26-86

Move in 3-5-86 at 8 1/2 - 330'

SE NE NW Sec. 7 Twp. 16 S, Rg. 28 X East
X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2040'	Base any	feet depth with	50	exs of	60/40 poz 6% gel 3% CC
2nd plug @ 1300'	Base clay	feet depth with	50	exs of	" " "
3rd plug @ 350'	30' out liner	feet depth with	50	exs of	" " "
4th plug @ 40' w/solid bridge		feet depth with	10	exs of	" " "
5th plug @ plug		feet depth with		exs of	
(2) Ratchole with 10				(b) Mousehole with	

PUSHER	TD 4337' FORMATION	SURFACE PIPE 8 1/2" @ 337	ANHYDRITE 2021' ELEVATION 2595	STARTING TIME & DATE	COMPLETION TIME & DATE	1st PLUG @ FT. W/ SX	2nd PLUG @ FT. W/ SX	3rd PLUG @ FT. W/ SX	4th PLUG @ FT. W/ SX	RAT HOLE CIRCULATED W/ SX	MOUSE HOLE CIRCULATED W/ SX	WATER WELL PLUGGED W/ SX	CEMENT COMPANY	TECHNICIAN
--------	--------------------	---------------------------	--------------------------------	----------------------	------------------------	----------------------	----------------------	----------------------	----------------------	---------------------------	-----------------------------	--------------------------	----------------	------------

STATE CORPORATION COMMISSION

MAR 31 1985

CONSERVATION DIVISION
Wichita, Kansas

1st 1550 w/ 50 SX TAG

2nd 1000 80 SX

3rd 300 w/ 40

4th 40-0