

1030221

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20.992 - 00-00
APPROX. SW NW NE , SEC. 6 , T 16 S, R 28 WXX
4050 feet N from SE corner
2310 feet W from SE corner

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name James Well # 1-6

Operator: Gear Petroleum Co., Inc.

County Lane

Name & Address 300 Sutton Place

Well Total Depth 4359 141.67 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 4 Month: July Year: 19 84

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1950' with 50 sx cement

RECEIVED

STATE CORPORATION COMMISSION

2nd plug at 900' with 50 sx cement

07-06-84

1111 06 51

3rd plug at 360' with 40 sx cement
solid bridge

CONSERVATION DIVISION

Wichita, Kansas

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 pm Day: 4 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1950' with 50 sx cement, 2nd plug at 900' with 50 sx

cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 7-16-84

Signed (TECHNICIAN)

INV. NO. 2546

AUG 3 1984

AUG 21 1984