

1030349

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NW NW NE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,109-0000 *R*

4950 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name James "A" Well # 1-6

Operator: Landmark Oil Exploration, Inc.  
Name & Address: 105 South Broadway, Suite 1040  
Wichita, KS 67202

County Lane Lane 141.21

Well Total Depth 4345 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 332 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 2 Month: January Year: 19 85

Plugging proposal received from Bob Kasper

(company name) White & Ellis - Great Bend (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1900' with 40 sx cement

2nd plug at 800' with 30 sx cement

3rd plug at 380' with 40 sx cement

4th plug <sup>solid bridge</sup> hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:30 am Day: 2 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1900' with 40 sx cement, 2nd plug at 800' with

30 sx cement, 3rd plug at 380' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement

STATE CORPORATION COMMISSION

JAN 09 1985

STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
(if additional description is necessary, use BACK of this form.)

I ~~did~~ / did not) observe this plugging.

DATE 1-16-85

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 6527