

1060190

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-20,868-00-00
C NE NW SEC. 6, T 16 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JAMES F WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE 143.00

OPERATOR LICENSE # 5086

WELL TOTAL DEPTH 4400 FEET

OPERATOR: PINTAIL PETROLEUM LTD PRODUCTION CSG: SIZE 5 1/2" @ 4108' WITH 150 SX

NAME AND ADDRESS 225 N MARKET #300 SURFACE CASING: SIZE 8 5/8" @ 285' WITH 175 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 11 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 3971-75, 3978-3982 TOP STAGED WITH 550 SX CEMENT.

BOTTOM PLUG PUMP 300# HULLS WITH 25 SX CEMENT. PUMP 14 SX GEL THEN 165 SX CEMENT.

PRESSURED TO 550#. SHUT IN WITH 500#. WENT DOWN BACKSIDE WITH 10 SX CEMENT. PRESSURED

TO 500#. SHUT IN WITH 500#.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 11 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT

BOTTOM PLUG PUMP 300# HULLS WITH 25 SX CEMENT. PUMP 14 SX GEL THEN 165 SX CEMENT.

PRESSURED TO 550#. SHUT IN WITH 500#. WENT DOWN BACKSIDE WITH 10 SX CEMENT. PRESSURED

TO 500#. SHUT IN WITH 500#.

REVISED
DATE: 1/25/00

REMARKS: USED 65/35 POZMIX 6% GEL BY ALLIED: NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier (TECHNICIAN) 01-25-00
FORM CP-2/3
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
01-25-00