

1 030765

DEC 25 1986

API NUMBER 15-101-21,355 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 100'  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

E SW SE NE SEC. 6, T 16 S, R 28 W/R  
2970 feet from S section line  
890 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name James C Well # 1

Operator: Abercrombie Drilling, Inc.  
Name & Address 801 Union Center  
Wichita, KS 67202

County Lane 121.55

Well Total Depth 3740 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 24 Month: 12 Year: 19 86

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie Drilling, Inc. (phone) 913-726-4850

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2553' GL  
Anhydrite 1977-2017'

1st plug at 2020' with 50 sx cement, 2nd plug at 870' with 80 sx cement,

3rd plug at 340' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:30 a.m. Day: 25 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2020' with 50 sx cement,

2nd plug at 870' with 80 sx cement,

3rd plug at 340' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

DEC 30 1986

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-30-86 (if not) observe this plugging.

Signed Steve Alverant  
(TECHNICIAN)

INV. NO. 15664  
12/25

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12-22-86 month day year

API Number 15-101-21,355-00-00 East 100' SW SE NE Sec. 6 Twp. 16 S. Rg. 28 X West 2970 890 Ft. from South Line of Section Ft. from East Line of Section

OPERATOR: License # 5422 Name Abercrombie Drilling, Inc. Address 801 Union Center City/State/Zip Wichita, KS 67202 Contact Person Jack L. Partridge Phone (316) 262-1841

CONTRACTOR: License # 5422 Name Abercrombie Drilling, Inc. City/State Wichita, Kansas

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 330 feet County Lane Lease Name James C Well # 1 Ground surface elevation 2553 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 2 X Depth to bottom of fresh water 150 Depth to bottom of usable water 127.5 Surface pipe planned to be set 300 Projected Total Depth 4950 feet Formation M, S, S, R, P, J, A, N

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 12-18-86 Signature of Operator or Agent Title Vice President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 6-18-87 Approved By 12-18-86

PLP 12-19-86 8 5/8" 300' surface pipe set

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug description, feet depth with, and size of cement. Includes entries for Base Anhydrite, Base Cheyenne Dakota, 30' below surface casing, Top 40', and Rathole with.

Handwritten log: Drilling, TD 3740 FORMATION Toronto, SURFACE PIPE 8 5/8 @ 309, ANHYDRITE 2017 ELEVATION 2553 GEL, STARTING TIME & DATE 9:00 a.m. - 12-24-86, COMPLETION TIME & DATE 12:30 p.m., 1st PLUG @ 2020 FT. W/ 50 SX, 2nd PLUG @ 870' FT. W/ 80 SX, 3rd PLUG @ 340 FT. W/ 50 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY B.J. Titon, 6940 W/ 670, TECHNICIAN

STATE CORPORATION COMMISSION DEC 30 1986 CONSERVATION DIVISION Wichita, Kansas