

NOV 18 1988

1 040205

API NUMBER 15-101-21,478 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NE, SEC. 5, T 16 S, R 28 W/E

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name Roberts Well # 1-5

Operator: Da Mar Resources, Inc.

County Lane 14381

Name & Address P.O. Box 70

Well Total Depth 4425 feet

Hays, KS 67601-0070

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: Day: 16 Month: 11 Year: 19 88

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4421'

1st plug sand back to 4375' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Plugging Proposal Received by Steve Pfeifer

DEC 21 1988

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: CONSERVATION DIVISION Wichita Kansas Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 5 sx cement on top of

sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.L. Titan. Recovered 3195' of 5 1/2" casing
(if additional description is necessary, use BACK of this form.)

INVOICED

(XXX) observe this plugging.

DEC 22 1988

DATE

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 23430