

1 030159

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,961 -00-00

SW SW NW, SEC. 5, T 16 S, R 28 (W)

2310 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7245

Lease Name James "B" Well # 1-5

Operator: Texas-El Dorado Oil Company

County Lane

Name & Address 550 West Central, Suite 1108

Well Total Depth 4500 146.25 feet

Wichita, KS 67203

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DNB Drilling, Inc. License Number 5476

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 6:00 am Day: 19 Month: April Year: 1984

Plugging proposal received from Jack Taylor

(company name) DNB (phone) 316-264-8328

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2040' with 50 sx cement 2nd plug at 1260' with 50 sx cement

3rd plug at 660' with 50 sx cement 4th plug at 330' with 40 sx cement
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rathole with 10 sx cement

Plugging Proposal Received by Steve Shumant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 am Day: 19 Month: April Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2040' with 50 sx cement, 2nd plug at 1260' with 50

sx cement, 3rd plug at 660' with 50 sx cement, 4th plug at 330' with 40 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx

cement. 7th plug to circulate rathole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun No. 17124

(If additional description is necessary, use BACK of this form. Wichita, Kansas)

(did not) observe this plugging.

Signed Steve Shumant
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1984
CONSERVATION DIVISION
Wichita, Kansas