

To: 1 11111111  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-101-20,178-00-00  
C NE SE, SEC. 4, T 16 S, R 28 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393  
Operator: A.L. Abercrombie, Inc.  
Name: \_\_\_\_\_  
Address Rt. 1, Box 56  
Great Bend, KS 67530

1980 feet from S section line  
660 feet from E section line  
Lease Name Shanline Well # 1  
County Lane  
Well Total Depth 4416 143.52 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 237

(-30)

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_  
Plugging Contractor A.L. Abercrombie, Inc. License Number 5393  
Address Rt. 1, Box 56, Great Bend, KS 67530

Company to plug at: Hour: 10:45 a.m. Day: 30 Month: 1 Year: 1996  
Plugging proposal received from Bill Sowles  
(company name) A.L. Abercrombie, Inc. (phone) 316-793-8186

Core: 4 1/2" at 4415' w/250 sx cement, PBSD 4376', Perfs at 4302-10'  
1st plug CIBP at 4270'. Well squeezed at 2849' with 75 sx cement. Cement at 2849'.  
2nd plug perforate at 1250', pump 80 sx cement,  
3rd plug pump 150 sx cement down backside.

RECEIVED  
KANSAS CORP COM  
1996 FEB - 2  
AC 11: 32

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 12 p.m. Day: 30 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4270'. Well squeezed at 2849' with 75 sx cement. Cement at 2849'.

2nd plug L-K Wireline perforated 4 1/2" casing at 1250' and pumped 190 sx cement down 4 1/2",  
3rd plug pumped 150 sx cement down 8 5/8" X 4 1/2". Shut in 50 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

~~INVOICED~~  
I (City) ~~XXXXXXX~~ observe this plugging.

DATE 2-6-96  
44825

Signed Kevin D. Shults  
(TECHNICIAN)