

1 050731

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,261 -00-00

NE NE SW, SEC. 33, T 16 S, R 28 (W) X

2310 feet from (S) section line

2970 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9560

Lease Name Terwilliger Well # 1

Operator: Burnette Oil & Gas

County Lane

Name &

Address 1205 North C Street

Well Total Depth 4666 Mississippi 151.65 feet

Wellington, KS 67152

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 3:30 am Day: 20 Month: December Year: 19 85

Plugging proposal received from Wayne Shively

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2767' Anhydrite 2170-2202

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:15 am Day: 20 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1285' with 80 sx

cement, 3rd plug at 400' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. # 928

(if additional description is necessary, use BACK of this form.)

11/27/85 did not observe this plugging.

DATE DEC 27 1985

DEC 27 1985

Signed Richard M. Long (TECHNICIAN)

INV NO 11732

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 11-25-85
month day year

API Number 15- 101-21,261-00-00

OPERATOR: License # ~~9580~~
Name Burnette Oil & Gas
Address 1205 N. C Street
City/State/Zip Wellington, KS 67152
Contact Person Jack L. Partridge
Phone 316-262-1841

NE, NE, SW, Sec 33 Twp 16, S, Rgr 28
(location)
2310 Ft North from Southeast Corner of Section
2970 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, KS 67202

Nearest lease or unit boundary line 330 feet
County Lane
Lease Name Terwilliger Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
X Oil Swd Infield Mud Rotary
Gas Inj Pool Ext. Air Rotary
 OWW Wildcat Cable

Depth to Bottom of fresh water 120 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 1100 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 350 feet
Conductor pipe if any required None feet
Ground surface elevation feet MSL.
This Authorization Expires 5-21-86
Approved By 11-21-85

If OWWO: old well info as follows:
Operator
Well Name
Cump Date Old Total Depth
Projected Total Depth 4650 feet
Projected Formation at TD Mississippian
Expected Producing Formations Mississippian

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

11-21-85
Signature of Operator or Agent Clarence W. Burnette
Clarence W. Burnette Title Owner/Operator
Form C-1 4/84

Speed 12-13-85
Set 350' + 8078

actual plugging

PUSHER	Wayne Shively
TD	4666' FORMATION Miss
SURFACE PIPE	5" @ 369'
ANHYDRITE	270' ELEVATION 2167'
STARTING TIME & DATE	12-20-85 3:30 AM
COMPLETION TIME & DATE	12-20-85 6:15 AM
1st PLUG @	220' FT. W/ 20 SX
2nd PLUG @	285' FT. W/ 30 SX
3rd PLUG @	400' FT. W/ 40 SX
4th PLUG @	400' FT. W/ 10 SX
FAT HOLE CIRCULATED W/	15' SX
MOUSE HOLE CIRCULATED W/	SX
WATER WELL PLUGGED W/	SX
CEMENT COMP	filled - 60/40 w/ 60% alone
TECHNICIAN	Alone
1st Bar	11' w/ 50 SX
2nd 50' Bar	Bar cherym w/ 50 SX
3rd 30' Bar	30' w/ 40 SX
4th SB	40' - 10 SX
6th R	115' - 614 P02