

1 070184

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,313-00-00

NW NW NW, SEC. 16, T 18 S, R 27 WXX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

4950 feet from S section line

4950 feet from E section line

Operator: Chief Drilling Co., Inc.
Name & Address: 151 N. Main, Suite 700
Wichita, KS 67202

Lease Name Hineman "B" Well # 1

County Lane 151.13

Well Total Depth 4650 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number 5886

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 9:10 am Day: 15 Month: May Year: 19 86

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2690'
Anhydrite 2066'

1st plug at 2100' with 50 sx cement

2nd plug at 1110' with 50 sx cement

3rd plug at 290' with 40 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:15 am Day: 15 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1100' with 50 sx cement, 3rd plug at 300' with 40 sx cement, 4th plug from 40' to surface with 10 sx cement,

5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
MAY 27 1986
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

DATE MAY 27 1986

Signed Dan Goodraet (TECHNICIAN)

INV. NO. 13972

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 5 6 86
month day year

API Number 15- 101-21,313-00-00

OPERATOR: License # 5886
Name Chief Drilling Co., Inc.
Address 151 N. Main Suite #700
City/State/Zip Wichita, Kansas 67202
Contact Person Douglas W. Thimesch
Phone 316-262-3791

— East
NW, NW, NW.. Sec. 16, Twp. 18, S, Rg. 27... X West
1950 Ft. from South Line of Section
1950 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5886
Name Warrior Drilling Co., Rig #2
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 330 feet
County Lane
Lease Name Lineman "B" Well #1
Ground surface elevation Will provide feet MSL
Domestic well within 330 feet: — yes X no
Municipal well within one mile: — yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 150
Depth to bottom of usable water 900 1100
Surface pipe planned to be set 260
Projected Total Depth 1600 feet
Formation Miss

Well Drilled For: Well Class: Type Equipment:
X Oil — SWD — Infield X Mud Rotary
— Gas — Inj — Pool Ext. — Air Rotary
— OWWO — Expl X Wildcat — Cable

If OWWO: old well info as follows:
Operator _____
Well Name _____
Comp Date _____ Old Total Depth _____

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
— cementing will be done immediately upon getting production casing.
Date 5-2-86 Signature of Operator or Agent Douglas W. Thimesch Title Vice President

For KCC Use:
Conductor Pipe Required _____ feet Minimum Surface Pipe Required 200 feet per Alt. 1 2
This Authorization Expires 11-2-86 Approved By _____

*Speed 5-6-86 1:30 PM
260' 8 5/8" will call back w/ 199' 31' dss*

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>2100</u>	feet depth with <u>50</u>	sxs of <u>60/40 posmix 3%cc 2%gel</u>
2nd plug @ <u>900 1110</u>	feet depth with <u>50</u>	sxs of _____
3rd plug @ <u>400 - 290</u>	feet depth with <u>40</u>	sxs of _____
4th plug @ <u>40</u>	feet depth with <u>10</u>	sxs of _____
5th plug @ _____	feet depth with _____	sxs of _____
(2) Rathole with <u>15</u> sxs		(b) Mousehole with <u>10</u> sxs

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.

PUSHER <u>Merion Stuss</u>	TD _____	FORMATION _____	ANHYDRITE _____	ELEVATION _____	STARTING TIME & DATE _____	COMPLETION TIME & DATE _____	1st PLUG @ _____ FT. W/ _____ SX	2nd PLUG @ _____ FT. W/ _____ SX	3rd PLUG @ _____ FT. W/ _____ SX	4th PLUG @ _____ FT. W/ _____ SX	RAT HOLE CIRCULATED W/ _____ SX	MOUSE HOLE CIRCULATED W/ _____ SX	WATER WELL PLUGGED W/ _____ SX	CEMENT COMPANY _____	TECHNICIAN _____
----------------------------	----------	-----------------	-----------------	-----------------	----------------------------	------------------------------	----------------------------------	----------------------------------	----------------------------------	----------------------------------	---------------------------------	-----------------------------------	--------------------------------	----------------------	------------------

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1986
CONSERVATION DIVISION
Wichita Kansas