

1 050594

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,203 -00-00  
C SE SW, SEC. 10, T 18 S, R 27 W/E

660 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Neeley Well # 2-10

Operator: Gear Petroleum Co., Inc.

County Lane Lane 150.80  
(Mississippi)

Name & Address 300 Sutton Place

Well Total Depth 4640 feet

Wichita, KS 67202

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well            Gas Well            Input Well            SWD Well            O&A X

Other well as hereinafter indicated           

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 10 Month: August Year: 1985

Plugging proposal received from Bruce Fickel

(company name) Red Tiger (phone) 316-263-2371

Elevation 2685 KB

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2043'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1150' with 80 sx cement

3rd plug 30' out of the surface pipe with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 7:00 am Day: 10 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2040' with 50 sx cement, 2nd plug at 1260' with 70

sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

*R.A.D.*

**INVOICED**

(if additional description is necessary, use BACK of this form.)

DATE 8-14-85

INV. NO. 9583

8-10

RECEIVED  
AUG 14 1985  
08-14-1985  
CONSERVATION DIVISION

Signed Richard W. Lacey  
(TECHNICIAN)