

1030423

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,171-00-00
NE NW SW, SEC. 10, T 18 S, R 27 W/E

4950 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Neeley Well # 1-10

Operator: Gear Petroleum Co., Inc.

County _____ Lane 150. PO

Name & Address 300 Sutton Place

Well Total Depth 4640 (Mississippi) feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 10:00 am Day: 25 Month: May Year: 19 85

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

Elevation 2686 KB

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2041-2075

1st plug at 2100' with 50 sx cement

2nd plug at 990' with 60 sx cement

3rd plug at 360' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:00 pm Day: 25 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 990' with 60

sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1985

05-31-1985
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 6-6-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 8342

JUN 25 1985 AUG 01 1985