

To: 1 110012
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,258-00-00

NW NW NE, SEC. 8, T 18 S, R 27 W/R
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5267 5205

Lease Name Spruill Trust Well # "C" 1

Operator: K & E Petroleum, Inc. &

County Lane 151.13

Name &

Address Mid-Continent Energy Corp.

Well Total Depth 4650 Mississippi feet

100 South Main, Suite 300

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 12:45 pm Day: 5 Month: December Year: 19 85

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2697 GL
Anhydrite 2080'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1350' with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by James R. Kapp

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:45 pm Day: 5 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2108' with 50 sx cement, 2nd plug at 1350' with 80 sx

cement, 3rd plug at 359' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 16 1985

INV. NO. 11525

12-5

DEC 12 1985
12-10-1985

CORP. & IND. DIV. OF
KANSAS DEPT. OF REVENUE

Signed

James R. Kapp
(TECHNICIAN)

FORM CP-2/3
Rev. 01-84

State of Kansas
NOTICE OF INTENTION TO DRILL
 (see rules on reverse side)

CARD MUST BE TYPED

CARD MUST BE SIGNED

(Starting Date: 12/1/85 month day year)

API Number 15- 101-21,258-00-00

OPERATOR: License # 5267 55205

NW NW NE Sec 8 Twp 18 S Rge 27 ☐ East ☒ West

Name K & E Petroleum, Inc. & Mid Continent Energy Corp.

Address 100 S. Main, Suite 300 Hardage

City/State/Zip Wichita, Kansas 67202

Contact Person Wayne L. Brinegar

Phone 316-264-4301

4950 Ft North from Southeast Corner of Section

2310 Ft West from Southeast Corner of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422

Name Abercrombie Drilling, Inc.

City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 330 feet

County Lane

Lease Name Spruill Trust "C" Well # 1

Domestic well within 330 feet: ☐ yes ☒ no

Municipal well within one mile: ☐ yes ☒ no

Well Drilled For: Well Class: Type Equipment:

☒ Oil ☐ Snd ☐ Infield ☒ Mud Rotary

☐ Gas ☐ Inj ☐ Pool Est. ☐ Air Rotary

☐ OWWO ☐ Expl ☒ Wildcat ☐ Cable

Depth to Bottom of fresh water 185 feet

Lowest usable water formation Dakota

Depth to Bottom of usable water 950 feet

Surface pipe by Alternate: 1 ☐ 2 ☒

Surface pipe to be set 350 feet

Conductor pipe if any required None feet

Ground surface elevation 2697 feet MSL

This Authorization Expires 5-20-86

Approved By 11-20-85 *LC*

If OWWO, old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

Projected Total Depth 4650 feet

Projected Formation at TD Mississippian

Expected Producing Formations Pennsylvanian

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 11/19/85 Signature of Operator or Agent

Wayne L. Brinegar

Title Vice-President, K & E Petroleum, Inc. Form C-F 4-84

Set 250' of 8 5/8" ann 11/27/85

11/27/85 2:00 PM Spud

PUSHER *Tommy Martin*

TD *4650'* FORMATION *Miss*

SURFACE PIPE *350 @ 8 5/8"*

ANHYDRITE *2080' ELEVATION 2697 ft*

STARTING TIME & DATE *12:45 11/27/85 2:00 PM*

COMPLETION TIME & DATE *2:45 PM 12-5-85*

1st PLUG @ *Bar Only 2108* FT. W/ *50* SX

2nd PLUG @ *1350* FT. W/ *80* SX

3rd PLUG @ *1359* FT. W/ *50* SX

4th PLUG @ *1401* FT. W/ *10* SX

1st of new hole *1401* BP *40'*

RAT HOLE CIRCULATED W/ *10* SX

MOUSE HOLE CIRCULATED W/ *10* SX

WATER WELL PLUGGED W/ *haul waste* SX

CEMENT COMPANY *BJT*

TECHNICIAN *Dan Gooch*

60/40 for 6 7/8 gel

DEC 10 1985
 12-10-1985