

1060167

8-13

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-21,554 -00-00
NE SW NW SEC. 8, T 18 S, R 27 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME EDWARDS C WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY LANE

OPERATOR LICENSE # 5123 WELL TOTAL DEPTH 4639 ^{150' 77} FEET

OPERATOR: PICKRELL DRILLING COMPANY, INC PRODUCTION CSG: SIZE 4 1/2" @ 4629' WITH 200 SX

NAME AND 110 N MARKET, SUITE 205 SURFACE CASING: SIZE 8 5/8" @ 267' WITH 155 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER _____

ADDRESS PO BOX 628 GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 13 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM J.D.

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: STAGE COLLAR @ 2080' WITH 275 SX CEMENT. CIRCULATED.

BOTTOM PLUG PUMP 300# HULLS AND 30 SX CEMENT.

PUMP 20 SX GEL THEN 125 SX CEMENT DOWN 4 1/2" CASING. PRESSURED TO 1000#. SHUT IN WITH

800#. WENT DOWN BACKSIDE WITH 15 SX CEMENT PRESSURED TO 500# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 13 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT _____

BOTTOM PLUG PUMP 300# HULLS AND 30 SX CEMENT.

PUMP 20 SX GEL THEN 125 SX CEMENT DOWN 4 1/2" CASING. PRESSURED TO 1000#. SHUT IN WITH

800#. WENT DOWN BACKSIDE WITH 15 SX CEMENT. PRESSURED TO 500# AND HELD.

08-30-1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED Michael J. Maier
(TECHNICIAN) FORM CP-2/3

DATE 8-31-99

INV. NO. 60448