

1 090005

131

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,519-00-00

W/2 NE SW SEC. 6, T 18 S, R 27 W/E

1830 feet from S section line

3790 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name Selfridge "SS" Well # 1

Operator: Slawson Exploration Company, Inc.
Name & Address: 104 South Broadway
Wichita, KS 67202

County Lane 15/61

Well Total Depth 4665 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 27 Month: 6 Year: 19 89

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2089-2119'

1st plug at 2100' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,

3rd plug at 340' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 12:15 p.m. Day: 27 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement,

2nd plug at 1200' with 80 sx cement,

3rd plug at 340' with 40 sx cement,

4th plug pumped 100 lbs. hulls, dropped 7 7/8" wiper plug and pumped 10 sx cement at 40',

5th plug pumped 15 sx cement into rathole.

Drilling mud used between plugs.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

INVOICED

DATE 7-5-89

INV. NO. 25168

Signed Michael R. Wilson (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JUN 24 1989 06-29-1989 CONSERVATION DIVISION Wichita, Kansas

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date June 17 1989
month day year

APP. W/2.NE.SW Sec 6 Twp 18 S, Rg 27 X East West

OPERATOR: License # 3988
Name: SLAWSON EXPLORATION COMPANY, INC.
Address: 104 South Broadway
City/State/Zip: Wichita, Kansas 67202
Contact Person: Jim Remsberg
Phone: (316) 263-3201

1830' feet from South line of Section
3790' feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 6039
Name: L.D. DRILLING, INC.

County: Lane
Lease Name: SELEBRIDGE "SS" Well # 1
Field Name: Wildcat
Is this a Prorated Field? yes X no
Target Formation(s): MISSISSIPPIAN
Nearest lease or unit boundary: 660'
Ground Surface Elevation: 2701' GR feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 200'
Depth to bottom of usable water: 1100'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 300'
Length of Conductor pipe required: None
Projected Total Depth: 4650' (MISS)
Formation at Total Depth: MISSISSIPPIAN
Water Source for Drilling Operations: (Irrigation Well)
well farm pond other
DWR Permit #: 6622
Will Cores Be Taken?: yes X no
If yes, proposed zone: _____

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location: _____

Spud 6-20-89

3/21 05/8
AFFIDAVIT 200' Alt. II Req.

PUSHER Greg Davidson
TD 4665 FORMATION Mississippi
SURFACE PIPE 8 9/8 @ 310
ANHYDRITE 2089-217 ELEVATION 2701
STARTING TIME & DATE 10:00 AM 6-27-89
COMPLETION TIME & DATE 12:15 PM 6-27-89
1st PLUG @ 2100 FT. W/ 50 SX
2nd PLUG @ 1200 FT. W/ 80 SX
3rd PLUG @ 340 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ _____ SX
WATER WELL PLUGGED W/ _____ SX

CEMENT COMPANY Allied
TECHNICIAN R.L.

RECEIVED
JUN 29 1989
06-29-1989
CONSERVATION DIVISION
Wichita, Kansas
within

5280	1320
4950	990
4620	660
4290	330
3960	
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - file acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.

18 27W