

4100269

TO: STATE CORPORATION COMMISSION

12-13

API NUMBER 15-101-21,765 -00-00  
110'W S/2 SW SW SEC. 5, T 18 S, R 27 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 550 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MCBEE WELL # 1-5

TECHNICIAN'S PLUGGING REPORT COUNTY LANE

OPERATOR LICENSE # 5030 WELL TOTAL DEPTH 4639 150.77 FEET

OPERATOR: VESS OIL CORPORATION PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND 8100 E 22ND ST N, BLDG 300 SURFACE CASING: SIZE 8 5/8" @ 305' WITH SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR L.D. DRILLING, INC LICENSE NUMBER 6039

ADDRESS RR 1, BOX 183-B, GREAT BEND, KS 67530-0183

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 13 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DORAN

(COMPANY NAME) L.D. DRILLING, INC (PHONE) 316-793-3051

WERE:

1ST PLUG AT 2100' WITH 50 SX CEMENT. 2ND PLUG AT 1200' WITH 80 SX CEMENT.

3RD PLUG AT 650' WITH 40 SX CEMENT. 4TH PLUG AT 330' WITH 50 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 6:30 PM DAY: 13 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2100' WITH 50 SX CEMENT. 2ND PLUG AT 1200' WITH 80 SX CEMENT.

3RD PLUG AT 650' WITH 40 SX CEMENT. 4TH PLUG AT 330' WITH 50 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1999  
01-07-1999  
CONSERVATION DIVISION  
Wichita, Kansas

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED Gary Winters  
(TECHNICIAN) FORM CP-2/3

1-12-99  
60524