

To: 1 070405
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEP 8 1987
API NUMBER 15- 101-21,410 -00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Operator: Hummon Corporation
Name & Address 400 One Main Place
Wichita, KS 67202

SW NE SW, SEC. 4, T 18 S, R 27 W/E
1650 feet from S section line
3630 feet from E section line

Lease Name Weiser Well # 1

County Lane 148.85

Well Total Depth 4580 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 8 Month: 9 Year: 19 87

Plugging proposal received from Rick Davis

(company name) H-30 Drilling Inc. (phone) 316-792-3586

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2597'
Anhydrite 2040'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at Base Cheyenne with 80 sx cement,

3rd plug at 30' below base of surface casing with 40 sx cement,

4th plug at 0-40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:45 p.m. Day: 8 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2040' with 50 sx cement,

2nd plug at 1700' with 80 sx cement,

3rd plug at 298' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

09-10-1987

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

(xxx) Observe this plugging.

DATE SEP 1 1 1987

Signed Dan Goodrow
(TECHNICIAN)

DATE 18082
9-8

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date August 28 1987

API Number 15-101-21, 410-00-00

OPERATOR: License # 5050
Name HUMMON CORPORATION
Address 400 One Main Place
City/State/Zip Wichita, Kansas 67202
Contact Person Kenneth S. White
Phone (316) 263-8521

SW NE SW Sec. 4 Twp. 18 S, Rg. 27
1650 Ft. from South Line of Section
3630 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County LANE

CONTRACTOR: License # 5107
Name H-30 Drilling, Inc.
City/State Wichita, Kansas

Lease Name Weiser Well # 1
Ground surface elevation 2597 feet MSL

Well Drilled For: Well Class: Type Equipment:
XX Oil SWD Infield XX Mud Rotary
Gas Inj Pool Est Air Rotary
OWWO Expl XX Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 100'
Depth to bottom of usable water 1200'

Surface pipe by Alternate: 1 XX

Surface pipe planned to be set 200'

Conductor pipe required NONE

Projected Total Depth 4600 feet

Formation Mississippi

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 8/21/87 Signature of Operator or Agent Kenneth S. White Title Vice President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2

This Authorization Expires 2-21-88 Approved By 8-21-87

Spud 8-30-87

NO WW

8 5/8" - 250'

SW NE SW Sec. 4 Twp. 18 S, Rg. 27 XX East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Base Anhydrite feet depth with 50
2nd plug @ Base Anhydrite feet depth with 80
3rd plug @ 30' Below Surf. Csg feet depth with 40
4th plug @ 0-40 feet depth with 10
5th plug @ feet depth with
(2) Rathole with 15 (b) Mousehole with 10

PUSHER Rick Davis
TD 4580 FORMATION MISS
SURFACE PIPE 8 5/8" @ 268
ANHYDRITE 2040 ELEVATION 2597
STARTING TIME & DATE 9:00pm 9-8-87
COMPLETION TIME & DATE 11:45pm 9-8-87
1st PLUG @ 2040 FT. W/ 50 SX
2nd PLUG @ 1700 FT. W/ 80 SX
3rd PLUG @ 298 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN Ray

D.G.
STATE CO.
09-10-1987