

To: 1 090341 10-12  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,388-00-01  
NE NW SW, SEC. 1, T 18 S, R 27 W/8  
2310 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Herl "A" Well # 1

Operator: Chief Drilling, Inc.

County Lane

Name:  
Address 120 S. Market, Ste. 300  
Wichita, KS 67202

Well Total Depth 4550 147.87 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 120 S. Market, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 12:20 p.m. Day: 12 Month: 10 Year: 1993

Plugging proposal received from Gary Lindenmuth

(company name) Chief Drilling, Inc. (phone) 316-262-3791

Work: 4 1/2" at 4548' w/200 sx cement, PBD 4333', Perfs at 4486-92, 4378-81, 4110-14', 4182-88'  
Cement from 1938-250'

1st plug pump 25 sx cement and 3 sx hulls over perfs.

2nd plug gel to 1938', 75 sx cement to surface,

Check backside.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15 p.m. Day: 12 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and 3 sx hulls over perfs,  
2nd plug gel to 1938, pumped 75 sx cement to surface. Maximum pressure 1000psi and shut in 800 psi  
3rd plug pumped 25 sx cement down backside. Maximum pressure 400 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

OCT 14 1993

(If additional description is necessary, use BACK of this form.)

DATE: 10-20-93  
Observe this plugging.

Signed [Signature]  
CONSERVATION DIVISION  
Wichita, Kansas  
(TECHNICIAN)

38989