

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20295-00-00  
Spot: CNENENW Sec/Twnshp/Rge: 22-17S-27W  
660 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: WHEATCROFT GLENC Well Number: 4  
County: LANE Total Vertical Depth: 4603 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W. 93 N.  
VALLEY CENTER, KS 67147

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 351  
Production: Size 5.5 feet: 4576 WITH 200 SX CMT  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2001 8:40 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC  
Proposal Revd. from: BILL SCHMIDT Company: PLAINS INC Phone: (785) 798-3995

Proposed Plugging Method: 1ST PLUG AT 4150' WITH 300# HULLS & 25 SX CMT THROUGH TUBING. PULL TUBING TO 2050' & CIRCULATE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/12/2001 1:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4601'. PERFS AT 4193-95', 4199-4201', 4221-24', & 4268-70'. DV TOOL @ 2049' CMT TO SURFACE (500 SX). RAN TUBING IN HOLE TO 4150'. SWIFT PUMPED DOWN 2 3/8" TUBING 25 SX CMT WITH 200# HULLS. PULLED TUBING TO 2800' (LEAK APPROX. 2850') PUMPED 15 SX CMT WITH 300# HULLS. PULLED TUBING UP TO 2050' PUMPED 165 SX CMT WITH 400# HULLS MIXED THROUGHOUT. HAD RETURNS WITH 110 SX MIX. WELL ON VACUUM. SHUT DOWN. ON 03/12/01 RAN TUBING IN HOLE TO 1250' TAGGED CMT. SWIFT SERVICES PUMPED 100 SX CMT. CIRCULATED TO SURFACE. TOPPED OF WITH 20 SX CMT. TESTED 8 5/8" X 5 1/2" ANNULUS TO 300#. PUMPED 3/4 BBL PER MINUTE & 50 SX. SHUT IN PRESSURE 150#.

INVOICED  
DATE 3-30-01  
2001061564

RECEIVED  
STATE CORPORATION COMMISSION

MAR 23 2001

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Kevin D. Strube  
(TECHNICIAN)

MAR 19 2001